

TRANSMITTAL LETTER TO THE
UNITED STATES RECEIVING OFFICE

Date	4 October 2000
International Application No.	
Attorney Docket No.	02649.012

I. Certification under 37 CFR 1.10 (if applicable)

EL 392 912 300 US
Express Mail mailing number

4 October 2000
Date of Deposit

I hereby certify that the application/correspondence attached hereto is being deposited with the United States Postal Service "Express Mail Post Office to Addressee" service under 37 CFR 1.10 on the date indicated above and is addressed to Assistant Commissioner for Patents, Washington, D.C. 20231.


Signature of person mailing correspondence

Kenneth E. Horton
Typed or printed name of person mailing correspondence

II. ☒ New International Application

EL 392912300US

TITLE	METHODS FOR IDENTIFICATION AND VERIFICATION
-------	---

Earliest priority date
(Day/Month/Year)

04/10/99

SCREENING DISCLOSURE INFORMATION: In order to assist in screening the accompanying international application for purposes of determining whether a license for foreign transmittal should and could be granted and for other purposes, the following information is supplied. (Note: check as many boxes as apply):

- A. ☐ The invention disclosed was not made in the United States.
 B. ☐ There is no prior U.S. application relating to this invention.
 C. ☒ The following prior U.S. application(s) contain subject matter which is related to the invention disclosed in the attached international application. (NOTE: priority to these applications may or may not be claimed on form PCT/RO/101 (Request) and this listing does not constitute a claim for priority.)

application no.	60/157,573	filed on	October 4, 1999
application no.		filed on	

- D. ☒ The present international application contains additional subject matter not found in the prior U.S. application(s) identified in paragraph C. above. The additional subject matter is found on pages 1 through 24 and ☐ DOES NOT ALTER ☒ MIGHT BE CONSIDERED TO ALTER the general nature of the invention in a manner which would require the U.S. application to have been made available for inspection by the appropriate defense agencies under 35 U.S.C. 181 and 37 CFR 5.1. See 37 CFR 5.15

III. ☐ A Response to an Invitation from the RO/US. The following document(s) is(are) enclosed:

- A. ☐ A Request for An Extension of Time to File a Response
 B. ☐ A Power of Attorney (General or Regular)
 C. ☐ Replacement pages:

pages		of the request (PCT/RO/101)	pages		of the figures
pages		of the description	pages		of the abstract
pages		of the claims			

- D. ☐ Submission of Priority Documents

Priority document		Priority document	
-------------------	--	-------------------	--

- E. ☐ Fees as specified on attached Fee Calculation sheet form PCT/RO/101 annex

IV. ☐ A Request for Rectification under PCT 91 ☐ A Petition ☐ A Sequence Listing Diskette


V. ☒ Other (please specify): Fee Calculation Sheet

The person
signing this
form is the:

- ☐ Applicant
☒ Attorney/Agent (Reg. No.)
 39,481
☐ Common Representative

Kenneth E. Horton

Typed Name of Signer



Signature

BEST AVAILABLE COPY

PCT

FEE CALCULATION SHEET

Annex to the Request

For receiving Office use only

International application No.

Date stamp of the receiving Office

Applicant's or agent's
file reference 02649.012

Applicant
EDAX Inc.

CALCULATION OF PRESCRIBED FEES

1. TRANSMITTAL FEE 240.00 T
2. SEARCH FEE 700.00 S

International search to be carried out by USPTO

(If two or more International Searching Authorities are competent in relation to the international application, indicate the name of the Authority which is chosen to carry out the international search.)

3. INTERNATIONAL FEE

Basic Fee

The international application contains 36 sheets.

first 30 sheets 427.00 b1

6 x 10.00 = 60.00 b1

remaining sheets additional amount

Add amounts entered at b1 and b2 and enter total at B 487.00 B

Designation Fees

The international application contains all designations.

8 x 92.00 = 736.00 D

number of designation fees amount of designation fee payable (maximum 11)

Add amounts entered at B and D and enter total at I 1,223.00 I

(Applicants from certain States are entitled to a reduction of 75% of the international fee. Where the applicant is (or all applicants are) so entitled, the total to be entered at I is 25% of the sum of the amounts entered at B and D.)

4. FEE FOR PRIORITY DOCUMENT (if applicable) 15.00 P

5 TOTAL FEES PAYABLE 2,178.00

Add amounts entered at T, S, I and P, and enter total in the TOTAL box TOTAL

☐ The designation fees are not paid at this time.

MODE OF PAYMENT

☐ authorization to charge deposit account (see below)

☐ bank draft

☐ coupons

☒ cheque

☐ cash

☐ other (specify):

☐ postal money order

☐ revenue stamps

DEPOSIT ACCOUNT AUTHORIZATION (this mode of payment may not be available at all receiving Offices)

The RO/ USPTO ☐ is hereby authorized to charge the total fees indicated above to my deposit account.

☒ is hereby authorized to charge any deficiency or credit any overpayment in the total fees indicated above to my deposit account.

☐ is hereby authorized to charge the fee for preparation and transmittal of the priority document to the International Bureau of WIPO to my deposit account.

50-0581

4 October 2000

Deposit Account No.

Date (day/month/year)

Signature

Ken Horton

PCT**REQUEST**

The undersigned requests that the present international application be processed according to the Patent Cooperation Treaty.

For receiving Office use only

International Application No.

International Filing Date

Name of receiving Office and "PCT International Application"

Applicant's or agent's file reference
(If desired) (12 characters maximum) 02649.012**Box No. I TITLE OF INVENTION**
METHODS FOR IDENTIFICATION AND VERIFICATION**Box No. II APPLICANT**

Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)

EDAX INC.

91 McKee

Mahwah, New Jersey 07430
US☐ This person is also inventor.

Telephone No.

(201) 529-4880

Facsimile No.

(201) 529-3156

Teleprinter No.

State (that is, country) of nationality:
USState (that is, country) of residence:
USThis person is applicant for the purposes of: ☐ all designated States ☒ all designated States except the United States of America ☐ the United States of America only ☐ the States indicated in the Supplemental Box**Box No. III FURTHER APPLICANT(S) AND/OR (FURTHER) INVENTOR(S)**

Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)

KAISER, Bruce John
6308 Christopher Winds Court
St. Louis, Missouri 63129
US

This person is:

☐ applicant only☐ applicant and inventor☒ inventor only (If this check-box is marked, do not fill in below.)State (that is, country) of nationality:
USState (that is, country) of residence:
USThis person is applicant for the purposes of: ☐ all designated States ☐ all designated States except the United States of America ☒ the United States of America only ☐ the States indicated in the Supplemental Box☒ Further applicants and/or (further) inventors are indicated on a continuation sheet.**Box No. IV AGENT OR COMMON REPRESENTATIVE; OR ADDRESS FOR CORRESPONDENCE**The person identified below is hereby/has been appointed to act on behalf of the applicant(s) before the competent International Authorities as: ☒ agent ☐ common representative

Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country.)

HORTON, Kenneth E.
PARSONS BEHLE & LATIMER
201 South Main Street, Suite 1800
Salt Lake City, Utah 84111
US

Telephone No.

(801) 536-6656

Facsimile No.

(801) 536-6111

Teleprinter No.

☐ Address for correspondence: Make this check-box where no agent or common representative is/has been appointed and the space above is used instead to indicate a special address to which correspondence should be sent.

Form PCT/RO/101 (first sheet) (July 1998)

See Notes to the request form

Continuation of Box No. III FURTHER APPLICANT(S) AND/OR (FURTHER) INVENTOR(S)	
<i>If none of the following sub-boxes is used, this sheet should not be included in the request.</i>	
<p>Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)</p> <p>PRICE, L. Stephen 2435 Harris Avenue Richland, Washington 99352 US</p>	<p>This person is:</p> <p><input type="checkbox"/> applicant only</p> <p><input type="checkbox"/> applicant and inventor</p> <p><input checked="" type="checkbox"/> inventor only (If this check-box is marked, do not fill in below.)</p>
State (that is, country) of nationality: US	State (that is, country) of residence: US
This person is applicant for the purposes of: <input type="checkbox"/> all designated States <input type="checkbox"/> all designated States except the United States of America <input checked="" type="checkbox"/> the United States of America only <input type="checkbox"/> the States indicated in the Supplemental Box	
<p>Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)</p> <p>KENNING, Don 9000 West Metaline Avenue Kennebec, Washington 99336 US</p>	<p>This person is:</p> <p><input type="checkbox"/> applicant only</p> <p><input type="checkbox"/> applicant and inventor</p> <p><input checked="" type="checkbox"/> inventor only (If this check-box is marked, do not fill in below.)</p>
State (that is, country) of nationality: US	State (that is, country) of residence: US
This person is applicant for the purposes of: <input type="checkbox"/> all designated States <input type="checkbox"/> all designated States except the United States of America <input checked="" type="checkbox"/> the United States of America only <input type="checkbox"/> the States indicated in the Supplemental Box	
<p>Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)</p> <p>WATSON, David J. 1109 Sanford Avenue Richland, Washington 99352 US</p>	<p>This person is:</p> <p><input type="checkbox"/> applicant only</p> <p><input type="checkbox"/> applicant and inventor</p> <p><input checked="" type="checkbox"/> inventor only (If this check-box is marked, do not fill in below.)</p>
State (that is, country) of nationality: US	State (that is, country) of residence: US
This person is applicant for the purposes of: <input type="checkbox"/> all designated States <input type="checkbox"/> all designated States except the United States of America <input checked="" type="checkbox"/> the United States of America only <input type="checkbox"/> the States indicated in the Supplemental Box	
<p>Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)</p> <p>KUHLMAN, Robert D. 1018 Winslow Avenue Richland, Washington 99352 US</p>	<p>This person is:</p> <p><input type="checkbox"/> applicant only</p> <p><input type="checkbox"/> applicant and inventor</p> <p><input checked="" type="checkbox"/> inventor only (If this check-box is marked, do not fill in below.)</p>
State (that is, country) of nationality: US	State (that is, country) of residence: US
This person is applicant for the purposes of: <input type="checkbox"/> all designated States <input type="checkbox"/> all designated States except the United States of America <input checked="" type="checkbox"/> the United States of America only <input type="checkbox"/> the States indicated in the Supplemental Box	
<input checked="" type="checkbox"/> Further applicants and/or (further) inventors are indicated on a continuation sheet.	

Continuation of Box No. III FURTHER APPLICANT(S) AND/OR (FURTHER) INVENTOR(S)

If none of the following sub-boxes is used, this sheet should not be included in the request.

Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)

NICOLOSI, Joseph A.
15 Joseph Lane
Bardonia, New York 10954
US

This person is:

- ☐ applicant only
☐ applicant and inventor
☒ inventor only (If this check-box is marked, do not fill in below.)

State (that is, country) of nationality:
US

State (that is, country) of residence:
US

This person is applicant for the purposes of: ☐ all designated States ☐ all designated States except the United States of America ☒ the United States of America only ☐ the States indicated in the Supplemental Box

Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)

MEYER, Gerhard A.
6734 Berend Street
Worthington, Ohio 43085
US

This person is:

- ☐ applicant only
☐ applicant and inventor
☒ inventor only (If this check-box is marked, do not fill in below.)

State (that is, country) of nationality:
US

State (that is, country) of residence:
US

This person is applicant for the purposes of: ☐ all designated States ☐ all designated States except the United States of America ☒ the United States of America only ☐ the States indicated in the Supplemental Box

Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)

This person is:

- ☐ applicant only
☐ applicant and inventor
☐ inventor only (If this check-box is marked, do not fill in below.)

State (that is, country) of nationality:

State (that is, country) of residence:

This person is applicant for the purposes of: ☐ all designated States ☐ all designated States except the United States of America ☐ the United States of America only ☐ the States indicated in the Supplemental Box

Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)

This person is:

- ☐ applicant only
☐ applicant and inventor
☐ inventor only (If this check-box is marked, do not fill in below.)

State (that is, country) of nationality:

State (that is, country) of residence:

This person is applicant for the purposes of: ☐ all designated States ☐ all designated States except the United States of America ☐ the United States of America only ☐ the States indicated in the Supplemental Box

☐ Further applicants and/or (further) inventors are indicated on a continuation sheet.

Box No. V DESIGNATION OF STATES

The following designations are hereby made under Rule 4.9(a) (mark the applicable check-boxes; at least one must be marked):

Regional Patent

- ☒ AP ARIPO Patent: GH Ghana, GM Gambia, KE Kenya, LS Lesotho, MW Malawi, SD Sudan, SZ Swaziland, UG Uganda, ZW Zimbabwe, and any other State which is a Contracting State of the Harare Protocol and of the PCT
- ☒ EA Eurasian Patent: AM Armenia, AZ Azerbaijan, BY Belarus, KG Kyrgyzstan, KZ Kazakhstan, MD Republic of Moldova, RU Russian Federation, TJ Tajikistan, TM Turkmenistan, and any other State which is a Contracting State of the Eurasian Patent Convention and of the PCT
- ☒ EP European Patent: AT Austria, BE Belgium, CH and LI Switzerland and Liechtenstein, CY Cyprus, DE Germany, DK Denmark, ES Spain, FI Finland, FR France, GB United Kingdom, GR Greece, IE Ireland, IT Italy, LU Luxembourg, MC Monaco, NL Netherlands, PT Portugal, SE Sweden, and another State which is a Contracting State of the European Patent Convention and of the PCT
- ☒ OA OAPI Patent: BF Burkina Faso, BJ Benin, CF Central African Republic, CG Congo, CI Côte d'Ivoire, CM Cameroon, GA Gabon, GN Guinea, ML Mali, MR Mauritania, NE Niger, SN Senegal, TD Chad, TG Togo, and any other State which is a member State of OAPI and a Contracting State of the PCT (if other kind of protection or treatment desired, specify on dotted line)

National Patent (if other kind of protection or treatment desired, specify on dotted line):

- | | |
|--|--|
| <input checked="" type="checkbox"/> AL Albania | <input checked="" type="checkbox"/> LS Lesotho |
| <input checked="" type="checkbox"/> AM Armenia | <input checked="" type="checkbox"/> LT Lithuania |
| <input checked="" type="checkbox"/> AT Austria | <input checked="" type="checkbox"/> LU Luxembourg |
| <input checked="" type="checkbox"/> AU Australia | <input checked="" type="checkbox"/> LV Latvia |
| <input checked="" type="checkbox"/> AZ Azerbaijan | <input checked="" type="checkbox"/> MD Republic of Moldova |
| <input checked="" type="checkbox"/> BA Bosnia and Herzegovina | <input checked="" type="checkbox"/> MG Madagascar |
| <input checked="" type="checkbox"/> BB Barbados | <input checked="" type="checkbox"/> MK the former Yugoslav Republic of Macedonia |
| <input checked="" type="checkbox"/> BG Bulgaria | |
| <input checked="" type="checkbox"/> BR Brazil | <input checked="" type="checkbox"/> MN Mongolia |
| <input checked="" type="checkbox"/> BY Belarus | <input checked="" type="checkbox"/> MW Malawi |
| <input checked="" type="checkbox"/> CA Canada | <input checked="" type="checkbox"/> MX Mexico |
| <input checked="" type="checkbox"/> CH and LI Switzerland and Liechtenstein | <input checked="" type="checkbox"/> NO Norway |
| <input checked="" type="checkbox"/> CN China | <input checked="" type="checkbox"/> NZ New Zealand |
| <input checked="" type="checkbox"/> CU Cuba | <input checked="" type="checkbox"/> PL Poland |
| <input checked="" type="checkbox"/> CZ Czech Republic | <input checked="" type="checkbox"/> PT Portugal |
| <input checked="" type="checkbox"/> DE Germany | <input checked="" type="checkbox"/> RO Romania |
| <input checked="" type="checkbox"/> DK Denmark | <input checked="" type="checkbox"/> RU Russian Federation |
| <input checked="" type="checkbox"/> EE Estonia | <input checked="" type="checkbox"/> SD Sudan |
| <input checked="" type="checkbox"/> ES Spain | <input checked="" type="checkbox"/> SE Sweden |
| <input checked="" type="checkbox"/> FI Finland | <input checked="" type="checkbox"/> SG Singapore |
| <input checked="" type="checkbox"/> GB United Kingdom | <input checked="" type="checkbox"/> SI Slovenia |
| <input checked="" type="checkbox"/> GE Georgia | <input checked="" type="checkbox"/> SK Slovakia |
| <input checked="" type="checkbox"/> GH Ghana | <input checked="" type="checkbox"/> SL Sierra Leone |
| <input checked="" type="checkbox"/> GM Gambia | <input checked="" type="checkbox"/> TJ Tajikistan |
| <input checked="" type="checkbox"/> GW Guinea-Bissau | <input checked="" type="checkbox"/> TM Turkmenistan |
| <input checked="" type="checkbox"/> HR Croatia | <input checked="" type="checkbox"/> TR Turkey |
| <input checked="" type="checkbox"/> HU Hungary | <input checked="" type="checkbox"/> TT Trinidad and Tobago |
| <input checked="" type="checkbox"/> ID Indonesia | <input checked="" type="checkbox"/> UA Ukraine |
| <input checked="" type="checkbox"/> IL Israel | <input checked="" type="checkbox"/> UG Uganda |
| <input checked="" type="checkbox"/> IS Iceland | <input checked="" type="checkbox"/> US United States of America |
| <input checked="" type="checkbox"/> JP Japan | |
| <input checked="" type="checkbox"/> KE Kenya | <input checked="" type="checkbox"/> UZ Uzbekistan |
| <input checked="" type="checkbox"/> KG Kyrgyzstan | <input checked="" type="checkbox"/> VN Viet Nam |
| <input checked="" type="checkbox"/> KP Democratic People's Republic of Korea | <input checked="" type="checkbox"/> YU Yugoslavia |
| | <input checked="" type="checkbox"/> ZW Zimbabwe |
| <input checked="" type="checkbox"/> KR Republic of Korea | Check-boxes reserved for designating States (for the purposes of |
| <input checked="" type="checkbox"/> KZ Kazakhstan | a national patent which have become party to the PCT after |
| <input checked="" type="checkbox"/> LC Saint Lucia | issuance of this sheet: |
| <input checked="" type="checkbox"/> LK Sri Lanka | <input type="checkbox"/> |
| <input checked="" type="checkbox"/> LR Liberia | <input type="checkbox"/> |

Precautionary Designation Statement: In addition to the designations made above, the applicant also makes under Rule 4.9(b) all other designations which would be permitted under the PCT except any designation(s) indicated in the Supplemental Box as being excluded from the scope of this statement. the applicant declares that those additional designations are subject to confirmation and that any designation which is not confirmed before the expiration of 15 months from the priority date is to be regarded as withdrawn by the applicant at the expiration of that time limit. (Confirmation of a designation consists of the filing of a notice specifying that designation and the payment of the designation and confirmation fees. Confirmation must reach the receiving Office within the 15-month time limit.)

Box No. VI PRIORITY CLAIM

Further priority claims are indicated in the Supplemental Box.

Filing date of earlier application (day/month/year)	Number of earlier application	Where earlier application is:		
		national application: country	Regional application: regional Office	international application: receiving Office
item (1) 04/10/99	60/157,573	US		
item (2)				
item (3)				

☒ The receiving Office is requested to prepare and transmit to the International Bureau a certified copy of the earlier application(s) (only if the earlier application was filed with the Office which for the purposes of the present international application is the receiving Office) identified above as item(s):

* Where the earlier application is an ARIPO application, it is mandatory to indicate in the Supplemental Box at least one country party to the Paris Convention for the Protection of Industrial Property for which that earlier application was filed (Rule 4.10(b)(ii)). See Supplemental Box.

Box No. VII INTERNATIONAL SEARCHING AUTHORITY

Choice of International Searching Authority (ISA)
(if two or more International Searching Authorities are competent to carry out the international search, indicate the Authority chosen; the two-letter code may be used):

Request to use results of earlier search; reference to that search (if an earlier search has been carried out by or requested from the International Searching Authority):

Date (day/month/year) Number Country (or regional Office)

ISA / USPTO

Box No. VIII CHECK LIST; LANGUAGE OF FILING

This international application contains the following number of sheets:

request : 5
description (excluding sequence listing part) : 19
claims : 4
abstract : 1
drawings : 7
sequence listing part of description :
Total number of sheets : 36

This international application is accompanied by the item(s) marked below:

1. ☒ fee calculation sheet
2. ☐ separate signed power of attorney
3. ☐ copy of general power of attorney; reference number, if any:
4. ☐ statement explaining lack of signature
5. ☐ priority document(s) identified in Box No. VI as item(s):
6. ☐ translation of international application into (language):
7. ☐ separate indications concerning deposited microorganism or other biological material
8. ☐ nucleotide and/or amino acid sequence listing in computer readable form
9. ☐ other (specify):

Figure of the drawings which should accompany the abstract:

4b

Language of filing of the international application:

English

Box No. IX SIGNATURE OF APPLICANT OR AGENT

Next to each signature, indicate the name of the person signing and the capacity in which the person signs (if such capacity is not obvious from reading the request).

EDAX INC.

By

Print Name JAMES AGARHSEN

Its TREASURER

For receiving Office use only

1. Date of actual receipt of the purported international application:	2. Drawings: <input type="checkbox"/> received: <input type="checkbox"/> not received:
3. Corrected date of actual receipt due to later but timely received papers or drawings completing the purported international application:	
4. Date of timely receipt of the required corrections under PCT Article 11(2):	
5. International Searching Authority (if two or more are competent): ISA /	6. <input type="checkbox"/> Transmittal of search copy delayed until search fee is paid.

Date of receipt of the record copy by the International Bureau:

For International Bureau use only

PARENT COOPERATION TREATY

PCT

NOTIFICATION OF THE RECORDING
OF A CHANGE(PCT Rule 92bis.1 and
Administrative Instructions, Section 422)

From the INTERNATIONAL BUREAU

To:

HORTON, Kenneth, E.
Rader, Fishman & Grauer PLLC
Suite 150
River Park Corporate Center One
10653 S. River Front Parkway
South Jordan, UT 84095
ETATS-UNIS D'AMERIQUE

Date of mailing (day/month/year)

23 octobre 2001 (23.10.01)

Applicant's or agent's file reference

02649.012

International application No.

PCT/US00/27492

IMPORTANT NOTIFICATION

International filing date (day/month/year)

04 octobre 2000 (04.10.00)

1. The following indications appeared on record concerning:

☐

the applicant

☐

the inventor

☒

the agent

☐

the common representative

Name and Address

HORTON, Kenneth, E.
Parsons Behle & Latimer
Suite 1800
201 South Main Street
Salt Lake City, UT 84111
United States of America

State of Nationality

State of Residence

Telephone No.

801-536-6656

Facsimile No.

801-536-6111

Teleprinter No.

2. The International Bureau hereby notifies the applicant that the following change has been recorded concerning:

☐

the person

☐

the name

☒

the address

☐

the nationality

☐

the residence

Name and Address

HORTON, Kenneth, E.
Rader, Fishman & Grauer PLLC
Suite 150
River Park Corporate Center One
10653 S. River Front Parkway
South Jordan, UT 84095
United States of America

State of Nationality

State of Residence

Telephone No.

801-572-0185

Facsimile No.

801-572-7666

Teleprinter No.

3. Further observations, if necessary:

4. A copy of this notification has been sent to:

☒

the receiving Office

☐

the International Searching Authority

☒

the International Preliminary Examining Authority

☐

the designated Offices concerned

☒

the elected Offices concerned

☐

other:

The International Bureau of WIPO
34, chemin des Colombettes
1211 Geneva 20, Switzerland

Facsimile No.: (41-22) 740.14.35

Authorized officer

Kari HUYNH-KHUONG

Telephone No.: (41-22) 338.83.38

PATENT COOPERATION TREATY

PCT

NOTIFICATION OF ELECTION

(PCT Rule 61.2)

From the INTERNATIONAL BUREAU

To:

Commissioner
US Department of Commerce
United States Patent and Trademark
Office, PCT
2011 South Clark Place Room
CP2/5C24
Arlington, VA 22202
ETATS-UNIS D'AMERIQUE
in its capacity as elected Office

Date of mailing (day/month/year)

16 August 2001 (16.08.01)

International application No.

PCT/US00/27492

Applicant's or agent's file reference

02649.012

International filing date (day/month/year)

04 October 2000 (04.10.00)

Priority date (day/month/year)

04 October 1999 (04.10.99)

Applicant

KAISER, Bruce, John et al

1. The designated Office is hereby notified of its election made:



in the demand filed with the International Preliminary Examining Authority on:

03 May 2001 (03.05.01)



in a notice effecting later election filed with the International Bureau on:

2. The election ☒ was



was not

made before the expiration of 19 months from the priority date or, where Rule 32 applies, within the time limit under Rule 32.2(b).

The International Bureau of WIPO
34, chemin des Colombettes
1211 Geneva 20, Switzerland

Facsimile No.: (41-22) 740.14.35

Authorized officer

Antonia Muller

Telephone No.: (41-22) 338.83.38

REC'D 22 NOV 2001

PCT

NOV 2001

PCT

INTERNATIONAL PRELIMINARY EXAMINATION REPORT

(PCT Article 36 and Rule 70)

Applicant's or agent's file reference 02649.012	FOR FURTHER ACTION See Notification of Transmittal of International Preliminary Examination Report (Form PCT/IPEA/416)	
International application No. PCT/US00/27492	International filing date (day/month/year) 04 October 2000 (04.10.2000)	Priority date (day/month/year) 04 October 1999 (04.10.1999)
International Patent Classification (IPC) or national classification and IPC IPC(7): G01N 23/223 and US Cl.: 378/44, 45		
Applicant EDAX INC.		
<p>1. This international preliminary examination report has been prepared by this International Preliminary Examining Authority and is transmitted to the applicant according to Article 36.</p> <p>2. This REPORT consists of a total of <u>3</u> sheets, including this cover sheet.</p> <p><input type="checkbox"/> This report is also accompanied by ANNEXES, i.e., sheets of the description, claims and/or drawings which have been amended and are the basis for this report and/or sheets containing rectifications made before this Authority (see Rule 70.16 and Section 607 of the Administrative Instructions under the PCT).</p> <p>These annexes consist of a total of <u>0</u> sheets.</p> <p>3. This report contains indications relating to the following items:</p> <p>I <input checked="" type="checkbox"/> Basis of the report</p> <p>II <input type="checkbox"/> Priority</p> <p>III <input type="checkbox"/> Non-establishment of report with regard to novelty, inventive step and industrial applicability</p> <p>IV <input type="checkbox"/> Lack of unity of invention</p> <p>V <input checked="" type="checkbox"/> Reasoned statement under Article 35(2) with regard to novelty, inventive step or industrial applicability; citations and explanations supporting such statement</p> <p>VI <input type="checkbox"/> Certain documents cited</p> <p>VII <input type="checkbox"/> Certain defects in the international application</p> <p>VIII <input type="checkbox"/> Certain observations on the international application</p>		
Date of submission of the demand 03 May 2001 (03.05.2001)	Date of completion of this report 25 September 2001 (25.09.2001)	
Name and mailing address of the IPEA/US Commissioner of Patents and Trademarks Box PCT Washington, D.C. 20231 Facsimile No. (703)305-3230	Authorized officer <i>Shawn S. Hope</i> David P. Porta Telephone No. 703-308-0956	

INTERNATIONAL PRELIMINARY EXAMINATION REPORT

International Application No.

PCT/US00/27492

I. Basis of the report

1. With regard to the elements of the international application:*

- ☒ the international application as originally filed.
- ☒ the description:
pages 1-19 _____ as originally filed
pages NONE _____, filed with the demand
pages NONE _____, filed with the letter of _____.
- ☒ the claims:
pages 20-23 _____, as originally filed
pages NONE _____, as amended (together with any statement) under Article 19
pages NONE _____, filed with the demand
pages NONE _____, filed with the letter of _____.
- ☒ the drawings:
pages 1-7 _____, as originally filed
pages NONE _____, filed with the demand
pages NONE _____, filed with the letter of _____.
- ☐ the sequence listing part of the description:
pages NONE _____, as originally filed
pages NONE _____, filed with the demand
pages NONE _____, filed with the letter of _____.

2. With regard to the language, all the elements marked above were available or furnished to this Authority in the language in which the international application was filed, unless otherwise indicated under this item.

These elements were available or furnished to this Authority in the following language _____ which is:

- ☐ the language of a translation furnished for the purposes of international search (under Rule 23.1(b)).
- ☐ the language of publication of the international application (under Rule 48.3(b)).
- ☐ the language of the translation furnished for the purposes of international preliminary examination (under Rules 55.2 and/or 55.3).

3. With regard to any nucleotide and/or amino acid sequence disclosed in the international application, the international preliminary examination was carried out on the basis of the sequence listing:

- ☐ contained in the international application in printed form.
- ☐ filed together with the international application in computer readable form.
- ☐ furnished subsequently to this Authority in written form.
- ☐ furnished subsequently to this Authority in computer readable form.
- ☐ The statement that the subsequently furnished written sequence listing does not go beyond the disclosure in the international application as filed has been furnished.
- ☐ The statement that the information recorded in computer readable form is identical to the written sequence listing has been furnished.

4. ☐ The amendments have resulted in the cancellation of:

- ☐ the description, pages NONE
- ☐ the claims, Nos. NONE
- ☐ the drawings, sheets/fig NONE

5. ☐ This report has been established as if (some of) the amendments had not been made, since they have been considered to go beyond the disclosure as filed, as indicated in the Supplemental Box (Rule 70.2(c)).**

* Replacement sheets which have been furnished to the receiving Office in response to an invitation under Article 14 are referred to in this report as "originally filed" and are not annexed to this report since they do not contain amendments (Rules 70.16 and 70.17).

** Any replacement sheet containing such amendments must be referred to under item 1 and annexed to this report.

INTERNATIONAL PRELIMINARY EXAMINATION REPORT

International application No.
PCT/US00/27492**V. Reasoned statement under Rule 66.2(a)(ii) with regard to novelty, inventive step or industrial applicability; citations and explanations supporting such statement****1. STATEMENT**

Novelty (N)	Claims <u>1-20</u>	YES
	Claims <u>NONE</u>	NO
Inventive Step (IS)	Claims <u>NONE</u>	YES
	Claims <u>1-20</u>	NO
Industrial Applicability (IA)	Claims <u>1-20</u>	YES
	Claims <u>NONE</u>	NO

2. CITATIONS AND EXPLANATIONS

Claims 1-20 lack an inventive step under PCT Article 33(3) as being obvious over Rabatin in view of Wortman et al. Rabatin discloses labeling packages with an X-ray taggant to identify the package. Rabatin fails to disclose that the tag is on a label. Wortman et al. teaches that it is well known to employ an X-ray fluorescent taggant on a label. It would have been obvious to one of ordinary skill in the art to employ the taggant on a label to provide a uniform taggant presentation to the analyzing unit.

Claims 1-20 meet the criteria set out in PCT Article 33(4), because the invention has applicability such as in tracking packages.

----- NEW CITATIONS -----
NONE

CORRECTED VERSION

(19) World Intellectual Property Organization
International Bureau



10/089900


(43) International Publication Date
12 April 2001 (12.04.2001)

PCT

(10) International Publication Number
WO 01/25768 A1

- (51) International Patent Classification⁷: G01N 23/223
- (21) International Application Number: PCT/US00/27492
- (22) International Filing Date: 4 October 2000 (04.10.2000)
- (25) Filing Language: English
- (26) Publication Language: English
- (30) Priority Data:
60/157,573 4 October 1999 (04.10.1999) US
- (71) Applicant (for all designated States except US): EDAX INC. [US/US]: 91 McKee, Mahwah, NJ 07430 (US).
- (72) Inventors: and
- (75) Inventors/Applicants (for US only): KAISER, Bruce, John [US/US]: 6308 Christopher Winds Court, St. Louis, MO 63129 (US). PRICE, L., Stephen [US/US]: 2435 Harris Avenue, Richland, WA 99352 (US). KENNING, Don [US/US]: 9000 West Metaline Avenue, Kennewick, WA 99336 (US). WATSON, David, J. [US/US]: 1109 Sanford Avenue, Richland, WA 99352 (US). KUHLMAN, Robert, D. [US/US]: 1018 Winslow Avenue, Richland, WA 99352 (US). NICOLosi, Joseph, A. [US/US]: 15 Joseph Lane, Bardonia, NY 10954 (US). MEYER, Gerhard, A. [US/US]: 6734 Berend Street, Worthington, OH 43085 (US).
- (74) Agent: HORTON, Kenneth, E.: Rader, Fishman & Grauer PLLC, Suite 150, River Park Corporate Center One, 10653 S. River Front Parkway, South Jordan, UT 84095 (US).
- (81) Designated States (national): AL, AM, AT, AU, AZ, BA, BB, BG, BR, BY, CA, CH, CN, CU, CZ, DE, DK, EE, ES, FI, GB, GE, GH, GM, HR, HU, ID, IL, IS, JP, KE, KG, KP, KR, KZ, LC, LK, LR, LS, LT, LU, LV, MD, MG, MK, MN, MW, MX, NO, NZ, PL, PT, RO, RU, SD, SE, SG, SI, SK, SL, TJ, TM, TR, TT, UA, UG, US, UZ, VN, YU, ZW.
- (84) Designated States (regional): ARIPO patent (GH, GM, KE, LS, MW, MZ, SD, SL, SZ, TZ, UG, ZW), Eurasian patent (AM, AZ, BY, KG, KZ, MD, RU, TJ, TM), European patent (AT, BE, CH, CY, DE, DK, ES, FI, FR, GB, GR, IE, IT, LU, MC, NL, PT, SE), OAPI patent (BF, BJ, CF, CG, CI, CM, GA, GN, GW, ML, MR, NE, SN, TD, TG).
- Published:
— with international search report
- (48) Date of publication of this corrected version:
16 May 2002
- (15) Information about Correction:
see PCT Gazette No. 20/2002 of 16 May 2002, Section II
- For two-letter codes and other abbreviations, refer to the "Guidance Notes on Codes and Abbreviations" appearing at the beginning of each regular issue of the PCT Gazette.

(54) Title: METHODS FOR IDENTIFICATION AND VERIFICATION



(57) Abstract: An apparatus and method in which one or more taggants that are intrinsically located or extrinsically placed in an article or product (11). The taggants are detected by X-ray fluorescence analysis (20, 21) to identify or verify the article or its point of manufacture. The taggants are manufactured as part of the article or the taggant is placed into a coating, label, or otherwise embedded within the article for the purpose of later verifying the presence or absence of these elements by X-ray fluorescence, thus determining the unique elemental composition of the taggant within the article.

WO 01/25768 A1

METHODS FOR IDENTIFICATION AND VERIFICATION

REFERENCE TO RELATED APPLICATIONS

This application is a continuation-in-part application of U.S. Provisional Application Serial No. 60/157,573, the disclosure of which is incorporated herein by reference.

FIELD OF THE INVENTION

The present invention generally relates to apparatus and methods for identification and verification. More particularly, the present invention relates to apparatus and methods for detecting an element or compound intrinsically present—or extrinsically added—in an article or product by using X-ray fluorescence to identify and verify that article or product.

BACKGROUND OF THE INVENTION

There has been significant interest in apparatus and methods for identifying and verifying various articles or products such as explosives, ammunition, paint, petroleum products, and documents. Known methods used to identify and verify generally involve adding and detecting materials like code-bearing microparticles, bulk chemical substances, and radioactive substances. Other methods used for identify and verify articles include those described in U.S. Patent Nos. 6,030,657, 6,024,200, 6,007,744, 6,005,915, 5,760,394, 5,474,937, 5,301,044, 5,208,630, 5,057,268, 4,862,143, 4,390,452, 4,363,965, and 4,045,676, the disclosures of which are incorporated herein by reference.

It is also known to apply materials to articles in order to track, for example, point of origin, authenticity, and their distribution. In one method, inks which are transparent in visible light are sometimes applied to materials and the presence (or absence) of the ink is revealed by ultraviolet or infrared fluorescence. Other methods

include implanting microscopic additives which can be detected optically. However, detecting these materials is primarily based on optical or photometric measurements.

Unfortunately, many of the apparatus and methods for identifying and verifying articles using such materials (called taggants) are unsatisfactory for several reasons. First, they are often difficult and time-consuming. In many instances, a sample of the article must be sent to an off-site laboratory for analysis. In other instances, the apparatus are often expensive, large, and difficult to operate. In yet other instances, the taggant used is radioactive, causing serious health concerns.

The known apparatus and methods for identification and verification are also unsatisfactory because they require a "line-of-sight" analysis method. This line of sight requirement entails that the apparatus must be able to "see" the taggant in order to detect it. This can be detracting when it would be desirable to detect the taggant without having to see the taggant, e.g., such as when the taggant is located in the middle of large package with packaging and labels "covering" the taggant.

SUMMARY OF THE INVENTION

The present invention provides an apparatus and method in which one or more taggants that are intrinsically located—or extrinsically placed—in an article or product are detected by x-ray fluorescence analysis to identify or verify the article or its point of manufacture. The taggants are manufactured as part of the article or the taggant is placed into a coating, packaging, label, or otherwise embedded within the article for the purpose of later verifying the presence or absence of these elements by x-ray fluorescence to determine the unique elemental composition of the taggant within these articles.

By using x-ray fluorescence analysis, the apparatus and methods of the present invention are simple and easy to use, as well as provide detection by a non line-of-sight method to establish the origin of materials, point of manufacture, authenticity, verification, or product security. The present invention is extremely advantageous because it is difficult to replicate, simulate, alter, transpose, or tamper. Further, it is easily recognizable by a user in either overt or covert form, verifiable by a

manufacturer or issuer, and is easily applicable to various forms of media in the articles.

BRIEF DESCRIPTION OF THE DRAWINGS

Figures 1, 2a, 2b, 3, 4a, 4b, and 5-7 are views of apparatus and methods for identification and verification according to the present invention. Figures 1, 2a, 2b, 3, 4a, 4b, and 5-7 presented in conjunction with this description are views of only particular—rather than complete—portions of apparatus and methods for identification and verification.

DETAILED DESCRIPTION OF THE INVENTION

The following description provides specific details in order to provide a thorough understanding of the present invention. The skilled artisan would understand, however, that the present invention can be practiced without employing these specific details. Indeed, the present invention can be practiced by modifying the illustrated apparatus and method and can be used in conjunction with apparatus and techniques conventionally used in the industry.

The present invention uses x-ray fluorescence analysis to detect at least one taggant which is intrinsically or extrinsically present in the material of a product or article. With x-ray fluorescence (XRF) analysis, x-rays produced from electron shifts in the inner shell(s) of atoms of the taggants and, therefore, are not effected by the form (chemical bonding) of the article being analyzed. The x-rays emitted from each element bear a specific and unique spectral signature, allowing one to determine whether that specific taggant is present in the product or article.

Figures 1, 2a, and 2b represent how it is believed XRF generally operates. In Figure 1, primary gamma rays or x-rays 40 are irradiated on a sample of a target material 46 of article 42. Secondary x-rays 44 are emitted from that sample of target material 46.

In Figures 2a and 2b, atom 48 of a taggant located within target material 46 has nucleus 50 surrounded by electrons 52 at discrete distances from nucleus 50 (called electron shells). Each electron shell has a binding energy level equal to the

amount of energy required to remove that electron from its corresponding shell. The innermost shell is the K shell, and has the highest binding energy level associated with it. Electron 54 is located within K shell 56.

Primary x-ray or gamma ray photon 40 impacting atom 48 has a given energy. If that energy is greater than the binding energy level of K shell 56, the energy of x-ray photon 40 is absorbed by atom 48, and one of the electrons in K shell 56 (i.e., electron 54) is ejected. With a vacancy now in K shell 56 left by electron 54, atom 48 is energetic and unstable. To become more stable, that vacancy in K shell 56 can be—and usually is—filled by an electron located in a shell with a lower binding energy level, such as L-shell electron 58 in L shell 60. As L-shell electron 58 fills the vacancy in K shell 56, atom 48 emits a secondary x-ray photon 44. The energy levels (or corresponding wavelengths) of such secondary x-ray photons are uniquely characteristic to each taggant, allowing the presence or absence of any specific taggant to be determined.

The at least one taggant can be intrinsically or extrinsically present in the product to be detected and/or its packaging (collectively, the “target material”). When the taggant(s) is intrinsically present, it is a component (either as an element, compound, or other type of composition) in at least one portion of that target material. When the taggant(s) is extrinsically present, it can be added, incorporated, or inserted into the target material as described below.

The at least one taggant employed in the present invention can be any suitable taggant known in the art. See, for example, U.S. Patent Nos. 5,474,937, 5,760,394, and 6,025,200, the disclosures of which are incorporated herein by reference. Suitable taggants include any element or compound which is capable of being detected via XRF. The type of elements that can be used as the taggant are theoretically any of those listed in the periodic table, but the lower energy emitted by electrons in the lower atomic-number elements could be a limiting factor. Such lower energies can be re-absorbed much easier into its own material matrix or, in some cases, into the ambient atmosphere (e.g. air). Further, different isotopes of an element, as well as elements which “excite” only under certain conditions—such as specific temperature

ranges—could be employed as the taggant in the present invention. Example of taggants that could be used in the present invention include any element with an atomic number ranging from 6 to 94. Preferably, rare earth metals are used as the at least one taggant in the present invention. More preferably, gadolinium (Gd) or lanthanum (LA) is used as the at least one taggant in the present invention.

The type of taggant depends, among other things, on the target material in which it is located. The target material can interfere with the XRF detection because, as described below, backscattering and peaks emitted by the composition of the target material during XRF analysis can interfere with the taggant peaks. For example, if paper packaging contained an As taggant and trace amounts of Pb existed in the paper, the K-level electrons of As and L-level electrons of Pb could give confusing readings during XRF detection.

In one aspect of the invention, the type of taggant should be selected based on the ability of the taggant and/or the substance in which it is located (i.e., a coating) to attach or bond to the target material. In many instances, the target material will be used, handled, and/or washed extensively. If the taggant (or the substance in which is located) is removed from the target material under such conditions, tagging the target material is of little value. For example, if a film or coating (e.g., ink) containing a taggant is applied to a target material (e.g., paper), the taggant and coating should be selected so that they will not be removed by the conditions to which the target material is periodically subjected (e.g., extensive contact with hands). Preferably, the coating and/or the taggant is selected in this aspect of the invention so that it chemically attaches or bonds to the target material, like paint attaches and bonds with a wall.

In another aspect of the invention, the type of taggant can be selected based on the ability of the taggant and/or the substance in which it is located (i.e., a coating) to be removed from the target material. In many instances, the purpose for which the target material is tagged will be temporary. After this purpose is completed, the taggant is no longer needed and can optionally be removed. For example, if an identifying film or coating containing a taggant is applied to a target material, once

the target material has been identified, the identifying film of coating may no longer be needed and can be removed by suitable means. Preferably, the coating and/or the taggant is selected in this aspect of the invention so that it is removable by mechanical or chemical means.

5 The amount and concentration of the taggant in the target material can also vary depending on the number of elements used and energy needed. The amount of taggant employed in the present invention is determined by the minimum amount needed for XRF detection. Additional amounts of taggant can be used as described below. The concentration of the taggant is at least about 1 part per million (ppm), and
10 can range from about 1-100 ppm. Larger taggant amounts can be used, but for economic reasons, a small amount is sufficient. Even lower taggant concentrations can be used (i.e., less than 1 ppm) as improved XRF devices and techniques become available.

 The form of the taggant in the target material can also vary. The form can be
15 any compound (i.e., salt) or molecule—either small or large—containing the element that is added by itself or with other components. Indeed, the taggant can be combined with various components and/or additives to make a mixture and/or solution. These other components or additives can be selected for various purposes, e.g., to modify the XRF properties, to modify the ability to be inserted into an article/product, to stabilize
20 the mixture or solution, or other purpose known in the chemical arts.

 In one aspect of the invention, the at least one taggant is a combination or plurality of taggants. A plurality of taggants could include more than one taggant of the same type, e.g., the same element or compound. A combination of taggants could also be more than one type of taggant, e.g., a different element or compound in
25 different media. For example, a taggant dispersed in ink which has been placed on paper which also contains the same or different taggant. The plurality of taggants could also include a combination of at least one intrinsic and at least one extrinsic taggant.

 The at least one taggant incorporated in the target material can provide a
30 distinctive code. Such a code could be based on the number and types of taggants

present or absent, an abundance ratio (i.e., concentrations) of the same or different taggants, the location of the taggants within the material (i.e., a barcode made of a series of taggants with a space, where the space could be part of the code), the presence of multiple types or forms of a single taggant, or a combination thereof.

5 As one example of such a code, the present invention can include a system in which the concentration of one taggant in a targeted material is controlled to provide a distinctive code. For example, for tagging ten commercially prepared batches of carpeting, the taggant yttrium oxide can be used. Ten unique codes could then be created for these ten batches by preparing samples of the target material containing
10 various concentrations (i.e., 10 ppm, 20 ppm, ... 100 ppm) of that taggant.

 The number of unique codes available with the use of just a single taggant depends on the precision with which that concentration can be controlled and measured in the sample. For example, if techniques allow concentrations in about 10 ppm increments, 10 unique codes (i.e., 10 ppm, 20 ppm, ... 100 ppm) can readily be
15 constructed from a single taggant for that concentration range. Additional codes could be created for larger concentration ranges, e.g., 100 codes of a concentration ranging from 10 ppm to 1000 ppm in 10 ppm increments. With the advent of superior concentration and detection techniques (e.g, for smaller increments), more codes may be constructed.

20 Further, the number of unique codes can be increased by adding additional types and concentrations of the same or different taggants. A significant increase in the number of possible codes can be achieved by using more than one taggant in creating the code. For example, the code can be expanded by adding another taggant with its own specific concentrations. The number of codes can be further expanded
25 by adding a third taggant with its own specific concentrations. Additional taggants could be used to provide even more codes. This coding system depends on the concentration increments of each of the taggants.

 The number of codes available in the coding system could also be increased by varying the location of the taggant(s) within the material to be detected. For example,
30 the detected material could be divided into any number of portions (i.e., quadrants)

with certain taggants (or codes) being placed in certain of those portions, and optionally not in others, to signify additional information during the XRF analysis.

When taggants include elements or compounds that may be found in the target material or in the environment to which the target material may be exposed, taggant contamination may occur and possibly render the taggant code difficult to read. For example, if the taggant comprising yttrium oxide is located in carpet as the targeted material, it is possible that additional amounts of the taggant(s) could be present in the targeted material as a result of environmental contamination, an internal chemical reaction, or other contamination. If this contamination occurs, there will be a change in the concentration of that taggant in the target material. Subsequent measurement of this taggant could yield a value corresponding to an incorrect code.

In such an instance, it is difficult to determine what amount of the taggant present in the targeted material is "contamination" as opposed to taggant present before contamination. This problem can be solved in target materials for which contamination might be suspected by using a backup (i.e., duplicate or otherwise) or secondary system, such as a backup or secondary taggant(s), backup or secondary code, or backup or secondary location. See, for example, the description in U.S. Patent No. 5,760,394, the disclosure of which is incorporated herein by reference. If desired, more than one such backup or secondary system can be used. The backup or secondary system can also be used for other purposes, e.g., to verify the original coding system.

Any suitable target material can be employed in the present invention. Suitable target materials include those which intrinsically contain the desired taggant(s) or in which the desired taggant(s) can be incorporated. Because XRF detection measures changes in the inner shell(s) of the taggant, it will not be significantly modified by chemical reactions which normally occur in the outer shells. Thus, it possible to tag chemicals and have the taggant code be carried in any product manufactured with those chemicals. Target materials should be comprised of a material in which XRF detection is easy, e.g., little chance of background

contamination, taggant deterioration, taggant destruction, contamination, or other deteriorating condition.

Example of suitable target materials include: paper products like documents, currency, or tickets; solid products like jewelry, carpets, packaging (films, labels, and adhesives), metals, rubbers (tires), woods, or plastics (credit cards); liquid products like lubricating fluids, resins, sprays, paints, oils, inks; hazardous wastes; drugs or pharmaceuticals; gaseous products; or combinations or hybrids of these materials. Additionally, suitable target materials—such as paper documents, drugs, or counterfeit manufactured items—include those that will be subsequently changed. For example, a target material that is suspected might be destroyed could be tagged with elements known to be present in the residue from the destruction. Since the taggant is not usually changed by the chemical process in destruction, a connection between the target material and its residue could be established after destruction. Preferably, the target material of the present invention is carpeting and carpet products.

The target materials containing the at least one taggant can be used for a wide number of applications. For example, tagging paints would allow any article coated with that paint to be identified. In another example, tagging paper and ink used in the paper (or applied to the paper) can be used to establish the authenticity of documents and currency. In yet another example, many manufactured items prone to counterfeiting or theft could benefit from tagging. Tagged threads in clothing could be used to encode information about the date, time, and place of manufacture. Tagging the bulk materials used in the manufacture of such items as compact disks, computer disks, video tapes, audio tapes, electronic circuits, and other items would be useful in tracing and prosecuting theft and counterfeiting cases involving these items. Tagging the packaging placed on products would allow quick and easy tracking of the packaged products.

In the present invention, the at least one taggant can be incorporated into the target material in any suitable form. Suitable forms include those which place that taggant in the target material with little to no damage (either chemical or physical) to

the target material. See, for example, the description in U.S. Patent Nos. 5,208,630, 5,760,394, and 6,030,657, the disclosures of which are incorporated herein by reference. Other suitable forms include using materials containing the taggant such as particulates like microparticles; solvents; coatings and films; adhesives; sprays; or a hybrid or combination of these methods. In any of these forms, the at least one taggant can be incorporated by itself or with another agent.

The at least one taggant can be incorporated in the target material using any suitable technique. Many existing tagging techniques involve the use of microparticles containing the elements, or compounds or compositions of the elements, comprising the at least one taggant. Additionally, particles can be manufactured wherein smaller particles, or compounds or compositions of the elements, containing the taggant. Such particles could be made of: magnetic or fluorescent materials to facilitate collection; refractory materials to enhance particle survival in an explosion; or chemically inert materials to enhance particle survival in a chemical reaction. Indeed, such particles could be made of non-durable, soluble, or reactive materials to enhance taggant dispersal in a fluid, aerosol, or powder system.

When the target material is a liquid article like paints, inks, or adhesives, or has a liquid component, the at least one taggant can be incorporated as an element or compound in solution with the liquid. Thus, the at least one taggant can be incorporated in elemental or compound form either in solution or suspension in the target material. The at least one taggant could also be dissolved or suspended in a solvent used in making the target material so that when that solvent evaporates, the residue left behind would contain the at least one taggant.

The taggant can be inserted into the target material of an article either during or after the article (or a part thereof) has been manufactured. The taggant can be manufactured as a component of the article or as part of a component of the article. During manufacture, the at least one taggant can also be incorporated into another material which comprises part of the article. Indeed, the at least one taggant could also be an element or compound of the article itself. The taggant can be incorporated into any location (including surfaces) of the article. Two (and three) dimensional

shapes and patterns of the at least one taggant can be constructed using any desired combination of types and numbers of taggants.

The at least one taggant could also be incorporated after manufacture of the target material of the article. The taggant can be implanted into the article or deposited as a coating or film on the article. Additionally, the at least one taggant could be incorporated into the already formed article as a dopant.

As a coating or film, the at least one taggant could be physically or chemically deposited by itself. The at least one taggant could also be incorporated as one ingredient (or contaminant) of another material (such as a mixture or solution) which forms a coating or film. In this aspect of the invention, the at least one taggant can be incorporated as an element or compound in solution (or suspension) with a liquid which is applied, such as by spraying, to the article. For example, the at least one taggant could be dissolved or suspended in a solvent so that when that solvent evaporates after being applied to the article, the residue left behind would contain the at least one taggant.

As apparent from the description above, the present invention has the ability to easily tag small batches of target materials with a code unique to that batch. This can be done manually or in an automated system where each batch (or select batches) of the target material receives a different code. For example, 1000 (or 100) compact discs could be manufacture and each could be tagged with a code of a number from 1 to 1000 (or 1 to 100). Economic and processing considerations, however, might limit the minimum size of each batch and the number of batches which could be tagged.

As described above, any product or article as the target material can have at least one extrinsic or intrinsic taggant located therein. For example, the target material of the present invention could be packaging and packaging products in one aspect of the invention. Examples of packaging and packaging products in which the at least one taggant could be intrinsically or extrinsically present include adhesives, boxes, labels, and wrapping, made of shrink-wrap materials, plastic materials, cardboards, laminates, papers, and the like.

In one aspect of the invention, the at least one taggant can be extrinsically or intrinsically present in any or all materials used for packaging. Examples of such packaging materials include boxes, wrapping, covers, films, coatings, and the like, as well as supplementary materials (since they supplement the packaging) such as tapes, adhesives, labels, inks, and the like.

The at least one taggant could be incorporated into packaging materials with each batch of material, if desired, having its own code. As one example, the paper label, adhesive, and/or cardboard box could have the at least one taggant incorporated therein. The taggant could be incorporated into the cardboard, paper, and/or adhesive material by injecting a solid (i.e., microparticle) or liquid (e.g., solvent) containing the at least one taggant into a component of the packaging material, e.g., the bulk material used in manufacturing the packaging. When the respective bulk material is used to make the cardboard, label, or adhesive (glue), the resulting packaging material(s) will contain the at least one taggant. Assuming six taggants will be used (two for the cardboard, two for the paper label, and two for the glue) a number of automated reservoirs having varying concentrations of the two taggants could be included in the assembly line process for each bulk material. Each reservoir would contain the distinctive mix of taggant concentrations, e.g., 5/5, 5/10, 5/15, ... 10/5, 10/10, 10/15, ... 95/85, 95/90, 95/95. As the sample of the respective bulk material passes through the assembly line, it would receive the taggants from the desired reservoir. Thus, packaging materials manufactured from its respective bulk material would receive a unique combination of taggants for its code.

After the at least one taggant is extrinsically or intrinsically present in the target material(s), the taggant(s) is detected to identify or verify the target material using XRF analysis as illustrated in Figure 1. Primary x-rays are used to excite a sample of the target material, and the secondary x-rays that are emitted by the sample are detected and analyzed.

As shown in Figure 3, the x-rays which are detected have various energies, e.g., there is a broad band of scattered x-rays with energies less than and greater than those of the exciting atom. Figure 3 illustrates this spectrum for paper as the target

material. Within this broad band, there are peaks due to the excitation of the taggant(s) in the sample. The ratio of the intensity of the radiation in any peak to the intensity of the background at the same energy (known as the peak-to-background ratio) is a measure of the concentration of the element which has characteristic X-rays at the energy of that peak, e.g., the taggant.

In one aspect of the detection method of the present invention, at least one target material believing to contain known concentrations of the taggant(s) of interest is selected. The XRF analysis is performed on that target material (or a sample thereof) using a detection device or apparatus containing an x-ray radiation source ("source"), x-ray radiation detector ("detector"), support means, analyzer means, and calibration means.

One aspect of the detection device of the present invention is illustrated in Figure 4a. In this Figure, the detection apparatus 25 has an ordinary x-ray fluorescence spectrometer capable of detecting elements present in a coating, package or material. X-rays 29 from a source (e.g., either x-ray tube or radioactive isotope) 20 impinge on a sample 11 which absorbs the radiation and emits x-rays 31 to an x-ray detector 21 and analyzer 23 capable of energy or wavelength discrimination. This is accomplished by using a commercially available x-ray spectrometer such as an Edax DX-95 or a MAP-4 portable analyzer, commercially available from Edax Inc., Mahwah, New Jersey. Part of analyzer 23 includes a computerized system 27.

Another aspect of the detection apparatus of the present invention is illustrated in Figure 4b. In this Figure, the detection apparatus 25 has an instrument housing 15 which contains the various components. Gamma rays or x-rays 30 from a source (e.g., either x-ray tube or radioactive isotope) 20 are optionally focused by aperture 10 to impinge on a sample 11. Sample 11 contains the at least one taggant which absorbs the radiation and emits x-rays 31 to an x-ray detector 21. Optionally, analyzing means can be incorporated within housing 15.

The present invention, however, is not limited to the detection apparatus depicted in Figures 4a and 4b. Any suitable source, or plurality of sources, known in the art can be used as the source in the detection device of the present. See, for

example, U.S. Patent Nos. 4,862,143, 4,045,676, and 6,005,915, the disclosures of which are incorporated herein by reference. During the XRF detection process, the source bombards the taggant with a high energy beam. The beam may be an electron beam or electromagnetic radiation such as X-rays or gamma rays. The source, therefore, may be any material which emits such high energy beams. Typically, these have been x-ray emitting devices such as x-ray tubes or radioactive sources.

To target, the beam can be focused and directed properly by any suitable means such as an orifice or an aperture. The configuration (size, length, diameter...) of the beam should be controlled, as known in the art, to obtain the desired XRF detection. The power (or energy level) of the source should also be controlled, as known in the art, to obtain the desired XRF detection.

The source(s) can be shielded and emit radiation in a space limited by the shape of the shield. Thus, the presence, configuration, and the material used for shielding the source should be controlled for consistent XRF detection. Any suitable material and configuration for that shield known in the art can be employed in the present invention. Preferably, any high-density materials used as the material for the shield, e.g, tungsten or brass.

Any suitable detector, or plurality of detectors, known in the art can be used as the detector in the detection device of the present invention. See, for example, U.S. Patent Nos. 4,862,143, 4,045,676, and 6,005,915, the disclosures of which are incorporated herein by reference. Any type of material capable of detecting the photons omitted by the taggant may be used. Silicon and CZT (cadmium-zinc-telluride) detectors have been conventionally used, but others such as proportional counters, germanium detectors, or mercuric iodide crystals can be used.

Several aspects of the detector should be controlled to obtain the desired XRF detection. First, the geometry between the detector and the target material should be controlled. The XRF detection also depend on the presence, configuration, and material—such as tungsten and beryllium—used as a window to allow x-rays photons to strike the detector. The age of the detector, voltage, humidity, variations in

exposure, and temperature can also impact the XRF detection and, therefore, these conditions should be controlled.

The analyzer means sorts the radiation detected by the detector into one or more energy bands and measures its intensity. Thus, any analyzer means performing this function could be used in the present invention. The analyzer means can be a multi-channel analyzer for measurements of the detected radiation in the characteristic band and any other bands necessary to compute the value of the characteristic radiation as distinct from the scattered or background radiation. See, for example, U.S. Patent Nos. 4,862,143, 4,045,676, and 6,005,915, the disclosures of which are incorporated herein by reference.

The XRF also depends on the resolution of the x-rays. Background and other noise must be filtered from the x-rays for proper measurement, e.g., the signals must be separated into the proper number of channels and excess noise removed. The resolution can be improved by cooling the detector using a thermoelectric cooler—such as nitrogen or a peltier cooler—and/or by filtering. Another way to improve this resolution is to use pre-amplifiers.

The support means supports the source and detector in predetermined positions relatively to a sample of the target material to be irradiated. Thus, any support means performing this function could be used in the present invention. In one example, the support means comprises two housings, where the source and detector are mounted in a first housing which is connected by a flexible cable to a second housing in which the analyzer means is positioned as illustrated in Figure 4a. If desired, the first housing may then be adapted to be hand-held. In another example, the source and detector as well as the other components of the detection device are mounted in a single housing as illustrated in Figure 4b.

The calibration means are used to calibrate the detection apparatus, thus insuring accuracy of the XRF analysis. In this calibration, the various parameters which could be modified and effect the measurement are isolated and calibrated. For example, the geometrical conditions or arrangements can be isolated and calibrated. In another example, the material matrix are isolated and calibrated. Preferably,

internal (*in situ*) calibration during detection is employed as the calibration means in the present invention. Components, such as tungsten shielding, are already present to internally calibrate during the XRF analysis. Other methods, such as fluorescence peak or Compton backscattering, could be used for internal calibration in the present invention.

Analyzer means, which includes a computerized system 27, is coupled to, receives, and processes the output signals produced by detector 21. The energy range of interest, which includes the energy levels of the secondary x-ray photons 44 emitted by the taggant(s), is divided into several energy subranges. Computerized system 27 maintains counts of the number of X-ray photons detected within each subrange using specific software programs, such as those to analyze the detection and x-ray interaction and to analyze backscatter data. After the desired exposure time, computerized system 27 with display menus stops receiving and processing output signals and produces a graph of the counts associated with each subrange.

Figure 5 is a representative graph of the counts associated with each subrange. This graph is essentially a histogram representing the frequency distribution of the energy levels E1, E2, and E3 of the detected x-ray photons. Peaks in the frequency distribution (i.e., relatively high numbers of counts) occur at energy levels of scattered primary x-ray photons as well as the secondary x-ray photons from the taggant(s). A primary x-ray photon incident upon a target material may be absorbed or scattered. The desired secondary x-ray photons are emitted only when the primary x-ray photons are absorbed. The scattered primary x-ray photons which reach the detector of the system create an unwanted background intensity level. Accordingly, the sensitivity of XRF analysis is dependent on the background intensity level, and the sensitivity of XRF detection may be improved by reducing the amount of scattered primary x-ray photons reaching the detector. The peak occurring at energy levels of scattered primary x-ray photons is basically ignored, while the other peaks—those occurring at E1, E2, and E3—are used to identify the at least one taggant present in the target material.

Besides the parameters described above, at least two other parameters must be controlled during the process of XRF detection. First, the media (such as air) through which the gamma rays (and x-rays) must travel also impacts the XRF. Therefore, the different types of media must be considered when performing the XRF analysis. Second, the methods used to interpret and analyze the x-rays depend, in large part, on the algorithms and software used. Thus, methods must be adopted to employ software and algorithms that will consistently perform the XRF detection.

These two parameters, plus those described above, must be carefully accounted for and controlled to obtain accurate measurements. In one aspect of the intention, these parameters could be varied and controlled to another provide a distinct code. For example, using a specific source and a specific detector with a specific measuring geometry and a specific algorithm could provide one distinct code. Changing the source, detector, geometry, or algorithm could provide a whole new set of distinct codes.

Figure 6 illustrates a preferred apparatus and detection method according to the present invention. In this Figure, detection apparatus 25 is capable of detecting at least one taggant present in packaging supplementary material, such as label 4 for a VCR tape 2. Detection apparatus 25 is a portable device which can be small enough to be hand-held. Detection apparatus 25 contains all the components discussed above (i.e., source, detector, analyzer means, and calibration means) in a single housing, thus allowing the portability and smaller size.

In Figure 6, VCR tape 2 had a tagged label 4 placed thereon using an adhesive (not shown). The VCR tape is enclosed in cover 8, along with paper brochures as advertising. The cover 8 is, in turn, covered with shrink wrap tape 10 as well as cardboard box 12. Detection apparatus 25 is able to detect the presence of the taggant(s) in label 4 even though the label is not in "line-of-sight" with the apparatus. Although not depicted in the aspect of the present invention shown in Figure 6, box 12, wrap 10, cover 8, and tape 2 could also have at least one taggant incorporated therein.

The present invention is not limited to any specific XRF analysis. Any type of XRF, such as total reflection x-ray fluorescence (TXRF), can be employed in the present invention.

5 In one aspect of the invention, the apparatus and method used identify an article once it has been tagged. The ability to invisibly tag an article and read the tag, especially through a non line-of-sight method, would provide an invaluable asset in any industry which authenticates, verifies, tracks, labels, or distributes goods of any kind. Indeed, having an invisible taggant(s) could further prevent copying and counterfeiting of goods. In another aspect of the invention, the apparatus and method
10 of the present invention could be used for these same purposes, but for those products which have the desired taggant already located therein. Thus, the present inventions could analyze liquid flows for contaminant particles or pinpoint via 3-D analysis the exact location of a contaminant(s) in an article.

The following non-limiting examples illustrate the present invention.

Example 1

15 A blank VCR tape with a plastic cover was purchased and the cover removed. A self-adhesive label was prepared for the tape. A taggant solution was then prepared by mixing 5 milliliters of adhesive solution with 0.352 grams of LaO_2 until a
20 homogenous mixture was obtained. The concentration of the taggant in the taggant solution was 5 wt%.

The taggant solution was then coated on the back of the label by hand and the label was then affixed to the VCR tape, and the plastic cover was then placed back on the tape. The cover was then shrink-wrapped with plastic tape and then placed inside
25 a cardboard box.

Example 2

The tagged adhesive on the label for the VCR from Example 1 was analyzed for the presence of the taggant. A portable, hand-held detection apparatus similar to

that illustrated in Figure 6 was used to detect the presence of the taggant using XRF analysis.

5 The detection apparatus contained several components. A trigger actuated tungsten shutter block containing an americium 241 gamma ray point source and a silicon pin x-ray detector were located within the front of the instrument. Circuit boards, necessary for acquiring and processing the data from the detector were located within the rest of the housing. The instrument had a red and a green light to indicate whether the carpet was tagged or not and a read out to inform the user that the carpet was tagged or not. A keypad on the top of the instrument allowed the user to turn the
10 electronics of the instrument on and off, while a key operated lock on the side of the instrument kept the user from inadvertently opening the shutter block, exposing the radioactive source.

This detection apparatus was used for an XRF analysis on the tagged sample. The result of the XRF analysis is reported in Figure 7. The peaks indicating the
15 presence of the LaO_2 taggant in Figure 7 are labeled.

Having described the preferred aspects of the present invention, it is understood that the invention defined by the appended claims is not to be limited by particular details set forth in the above description, as many apparent variations thereof are possible without departing from the spirit or scope thereof.

CLAIMSI claim:

1. A method for detecting at least one taggant in the packaging material
5 for an article, comprising:

providing the at least one taggant in at least a portion of the packaging
material;

causing the at least one taggant to radiate at least one x-ray; and

analyzing whether the at least one x-ray has a specific energy.

10 2. The method of claim 1, wherein the packaging material is at least one
label.

3. A method of analyzing the packaging material for an article,
comprising

15 providing at least a portion of a packaging material on or over a portion of an
article;

irradiating the packaging material portion with an energy beam; and

analyzing whether the packaging material portion irradiates at least one x-ray
with a specific energy.

20 4. The method of claim 3, wherein the packaging material is at least one
label.

5. A method for packaging an article, comprising:

providing a portion of an article; and

25 providing at least a portion of a packaging material on or over a portion of the
article, the packaging material portion comprising at least one taggant which radiates
at least one x-ray when an energy beam is impinged thereon.

6. The method of claim 5, wherein the packaging material is at least one
label.

30 7. Packaging material for an article, the packaging material comprising at
least one taggant which radiates at least one x-ray when an energy beam is impinged
thereon.

8. The packaging material of claim 7, wherein the packaging material is at least one label.

9. A method for manufacturing a packaging material containing at least one taggant, comprising:

5 providing a component of the packaging material;
 adding at least one taggant to the component, the at least one taggant radiating at least one x-ray when an energy beam is impinged thereon; and
 combining the tagged component with other components of the packaging material.

10 10. A method for manufacturing a packaging material containing at least one taggant, comprising:

 providing at least a portion of a packaging material; and
 adding at least one taggant to the packaging material portion, wherein the at least one taggant radiates at least one x-ray when an energy beam is impinged thereon.

15 11. A method of manufacturing a packaged article containing at least one taggant, comprising:

 providing a portion of an article; and
 providing a portion of a packaging material on or over a portion of the article, the packaging material comprising at least one taggant which radiates at least one x-ray when an energy beam is impinged thereon.

20 12. The method of claim 11, wherein the packaging material is at least one label.

 13. A packaged article containing at least one taggant made by the method comprising:

25 providing a portion of an article; and

providing a portion of a packaging material on or over a portion of the article, the packaging material comprising at least one taggant which radiates at least one x-ray when an energy beam is impinged thereon.

14. The packaged article of claim 13, wherein the packaging material is at least one label.

15. An article comprising a packaging material containing at least one taggant which radiates at least one x-ray when an energy beam is impinged thereon.

16. The article of claim 15, wherein the packaging material is at least one label.

17. A method of tagging an article with at least one taggant comprising: providing a portion of an article; and providing a portion of a packaging material on or over a portion of the article, the packaging material comprising at least one taggant which radiates at least one x-ray when an energy beam is impinged thereon.

18. The method of claim 17, wherein the packaging material is at least one label.

19. A packaging material containing at least one taggant made by the method comprising:

providing a component of the packaging material;

adding at least one taggant to the component, the at least one taggant radiating at least one x-ray when an energy beam is impinged thereon; and

combining the tagged component with other components of the packaging material.

20. A packaging material containing at least one taggant made by the method comprising:

providing at least a portion of a packaging material; and

adding the at least one taggant to the packaging material portion, wherein the at least one taggant radiates at least one x-ray when an energy beam is impinged thereon.




FIG. 1




FIG. 2b




FIG. 2a




FIG. 3

3 / 7




FIG. 4a

4 / 7






FIG. 4b

5 / 7

**FIG. 5**

6/7

**FIG. 6**




FIG. 7

INTERNATIONAL SEARCH REPORT

International application No.

PCT/US00/27492

A. CLASSIFICATION OF SUBJECT MATTER

IPC(7) : G01N 23/223

US CL : 378/44, 45

According to International Patent Classification (IPC) or to both national classification and IPC

B. FIELDS SEARCHED

Minimum documentation searched (classification system followed by classification symbols)

U.S. : 378/44, 45, 48, 49, 50

Documentation searched other than minimum documentation to the extent that such documents are included in the fields searched
NONE

Electronic data base consulted during the international search (name of data base and, where practicable, search terms used)
NONE

C. DOCUMENTS CONSIDERED TO BE RELEVANT

Category *	Citation of document, with indication, where appropriate, of the relevant passages	Relevant to claim No.
Y	US 4,485,308 A (RABATIN) 27 November 1984 (27.11.1984), column 3, lines 23-53.	1-20
Y	US 4,136,778 A (WORTMAN et al.) 30 JAN. 1979 (30.01.1979) column 4, lines 10-30.	1-20
A	US 4,445,225 A (WHITE) 24 April 1984 (24.04.1984) entire document.	1-20

☐ Further documents are listed in the continuation of Box C.

☐ See patent family annex.

* Special categories of cited documents:

"A" document defining the general state of the art which is not considered to be of particular relevance

"E" earlier application or patent published on or after the international filing date

"L" document which may throw doubts on priority claim(s) or which is cited to establish the publication date of another citation or other special reason (as specified)

"O" document referring to an oral disclosure, use, exhibition or other means

"P" document published prior to the international filing date but later than the priority date claimed

"T"

later document published after the international filing date or priority date and not in conflict with the application but cited to understand the principle or theory underlying the invention

"X"

document of particular relevance; the claimed invention cannot be considered novel or cannot be considered to involve an inventive step when the document is taken alone

"Y"

document of particular relevance; the claimed invention cannot be considered to involve an inventive step when the document is combined with one or more other such documents, such combination being obvious to a person skilled in the art

"&"

document member of the same patent family

Date of the actual completion of the international search

24 January 2001 (24.01.2001)

Date of mailing of the international search report

09 FEB 2001

Name and mailing address of the ISA/US

Commissioner of Patents and Trademarks
Box PCT
Washington, D.C. 20231

Facsimile No. (703) 305-3230

Authorized officer

David P. Porta

Telephone No. (703) 308-0956

Shawn J. Hopper

(19) World Intellectual Property Organization
International Bureau




(43) International Publication Date
12 April 2001 (12.04.2001)

PCT

(10) International Publication Number
WO 01/25768 A1

- (51) International Patent Classification⁷: G01N 23/223
- (21) International Application Number: PCT/US00/27492
- (22) International Filing Date: 4 October 2000 (04.10.2000)
- (25) Filing Language: English
- (26) Publication Language: English
- (30) Priority Data:
60/157,573 4 October 1999 (04.10.1999) US
- (71) Applicant (for all designated States except US): EDAX INC. [US/US]; 91 McKee, Mahwah, NJ 07430 (US).
- (72) Inventors; and
- (75) Inventors/Applicants (for US only): KAISER, Bruce, John [US/US]; 6308 Christopher Winds Court, St. Louis, MO 63129 (US). PRICE, L., Stephen [US/US]; 2435 Harris Avenue, Richland, WA 99352 (US). KENNING, Don [US/US]; 9000 West Metaline Avenue, Kennewick, WA 99336 (US). WATSON, David, J. [US/US]; 1109 Sanford Avenue, Richland, WA 99352 (US). KUHLMAN, Robert, D. [US/US]; 1018 Winslow Avenue, Richland, WA 99352 (US). NICOLOSI, Joseph, A. [US/US]; 15 Joseph Lane, Bardonia, NY 10954 (US). MEYER, Gerhard, A. [US/US]; 6734 Berend Street, Worthington, OH 43085 (US).
- (74) Agent: HORTON, Kenneth, E.; Parsons Behle & Latimer, Suite 1800, 201 South Main Street, Salt Lake City, UT 84111 (US).
- (81) Designated States (*national*): AL, AM, AT, AU, AZ, BA, BB, BG, BR, BY, CA, CH, CN, CU, CZ, DE, DK, EE, ES, FI, GB, GE, GH, GM, HR, HU, ID, IL, IS, JP, KE, KG, KP, KR, KZ, LC, LK, LR, LS, LT, LU, LV, MD, MG, MK, MN, MW, MX, NO, NZ, PL, PT, RO, RU, SD, SE, SG, SI, SK, SL, TJ, TM, TR, TT, UA, UG, US, UZ, VN, YU, ZW.
- (84) Designated States (*regional*): ARIPO patent (GH, GM, KE, LS, MW, MZ, SD, SL, SZ, TZ, UG, ZW), Eurasian patent (AM, AZ, BY, KG, KZ, MD, RU, TJ, TM), European patent (AT, BE, CH, CY, DE, DK, ES, FI, FR, GB, GR, IE, IT, LU, MC, NL, PT, SE), OAPI patent (BF, BJ, CF, CG, CI, CM, GA, GN, GW, ML, MR, NE, SN, TD, TG).
- Published:**
- With international search report.
 - Before the expiration of the time limit for amending the claims and to be republished in the event of receipt of amendments.
- For two-letter codes and other abbreviations, refer to the "Guidance Notes on Codes and Abbreviations" appearing at the beginning of each regular issue of the PCT Gazette.

(54) Title: METHODS FOR IDENTIFICATION AND VERIFICATION



(57) Abstract: An apparatus and method in which one or more taggants that are intrinsically located or extrinsically placed in an article or product (11). The taggants are detected by X-ray fluorescence analysis (20, 21) to identify or verify the article or its point of manufacture. The taggants are manufactured as part of the article or the taggant is placed into a coating, label, or otherwise embedded within the article for the purpose of later verifying the presence or absence of these elements by X-ray fluorescence, thus determining the unique elemental composition of the taggant within the article.

WO 01/25768 A1

5

METHODS FOR IDENTIFICATION AND VERIFICATION

REFERENCE TO RELATED APPLICATIONS

10

This application is a continuation-in-part application of U.S. Provisional Application Serial No. 60/157,573, the disclosure of which is incorporated herein by reference.

FIELD OF THE INVENTION

15

The present invention generally relates to apparatus and methods for identification and verification. More particularly, the present invention relates to apparatus and methods for detecting an element or compound intrinsically present—or extrinsically added—in an article or product by using X-ray fluorescence to identify and verify that article or product.

BACKGROUND OF THE INVENTION

20

25

There has been significant interest in apparatus and methods for identifying and verifying various articles or products such as explosives, ammunition, paint, petroleum products, and documents. Known methods used to identify and verify generally involve adding and detecting materials like code-bearing microparticles, bulk chemical substances, and radioactive substances. Other methods used for identify and verify articles include those described in U.S. Patent Nos. 6,030,657, 6,024,200, 6,007,744, 6,005,915, 5,760,394, 5,474,937, 5,301,044, 5,208,630, 5,057,268, 4,862,143, 4,390,452, 4,363,965, and 4,045,676, the disclosures of which are incorporated herein by reference.

30

It is also known to apply materials to articles in order to track, for example, point of origin, authenticity, and their distribution. In one method, inks which are transparent in visible light are sometimes applied to materials and the presence (or absence) of the ink is revealed by ultraviolet or infrared fluorescence. Other methods

include implanting microscopic additives which can be detected optically. However, detecting these materials is primarily based on optical or photometric measurements.

Unfortunately, many of the apparatus and methods for identifying and verifying articles using such materials (called taggants) are unsatisfactory for several reasons. First, they are often difficult and time-consuming. In many instances, a sample of the article must be sent to an off-site laboratory for analysis. In other instances, the apparatus are often expensive, large, and difficult to operate. In yet other instances, the taggant used is radioactive, causing serious health concerns.

The known apparatus and methods for identification and verification are also unsatisfactory because they require a "line-of-sight" analysis method. This line of sight requirement entails that the apparatus must be able to "see" the taggant in order to detect it. This can be detracting when it would be desirable to detect the taggant without having to see the taggant, e.g., such as when the taggant is located in the middle of large package with packaging and labels "covering" the taggant.

SUMMARY OF THE INVENTION

The present invention provides an apparatus and method in which one or more taggants that are intrinsically located—or extrinsically placed—in an article or product are detected by x-ray fluorescence analysis to identify or verify the article or its point of manufacture. The taggants are manufactured as part of the article or the taggant is placed into a coating, packaging, label, or otherwise embedded within the article for the purpose of later verifying the presence or absence of these elements by x-ray fluorescence to determine the unique elemental composition of the taggant within these articles.

By using x-ray fluorescence analysis, the apparatus and methods of the present invention are simple and easy to use, as well as provide detection by a non line-of-sight method to establish the origin of materials, point of manufacture, authenticity, verification, or product security. The present invention is extremely advantageous because it is difficult to replicate, simulate, alter, transpose, or tamper. Further, it is easily recognizable by a user in either overt or covert form, verifiable by a

manufacturer or issuer, and is easily applicable to various forms of media in the articles.

BRIEF DESCRIPTION OF THE DRAWINGS

5 Figures 1, 2a, 2b, 3, 4a, 4b, and 5-7 are views of apparatus and methods for identification and verification according to the present invention. Figures 1, 2a, 2b, 3, 4a, 4b, and 5-7 presented in conjunction with this description are views of only particular—rather than complete—portions of apparatus and methods for identification and verification.

DETAILED DESCRIPTION OF THE INVENTION

10 The following description provides specific details in order to provide a thorough understanding of the present invention. The skilled artisan would understand, however, that the present invention can be practiced without employing these specific details. Indeed, the present invention can be practiced by modifying the illustrated apparatus and method and can be used in conjunction with apparatus and
15 techniques conventionally used in the industry.

 The present invention uses x-ray fluorescence analysis to detect at least one taggant which is intrinsically or extrinsically present in the material of a product or article. With x-ray fluorescence (XRF) analysis, x-rays produced from electron shifts in the inner shell(s) of atoms of the taggants and, therefore, are not effected by the
20 form (chemical bonding) of the article being analyzed. The x-rays emitted from each element bear a specific and unique spectral signature, allowing one to determine whether that specific taggant is present in the product or article.

 Figures 1, 2a, and 2b represent how it is believed XRF generally operates. In Figure 1, primary gamma rays or x-rays 40 are irradiated on a sample of a target
25 material 46 of article 42. Secondary x-rays 44 are emitted from that sample of target material 46.

 In Figures 2a and 2b, atom 48 of a taggant located within target material 46 has nucleus 50 surrounded by electrons 52 at discrete distances from nucleus 50 (called electron shells). Each electron shell has a binding energy level equal to the

amount of energy required to remove that electron from its corresponding shell. The innermost shell is the K shell, and has the highest binding energy level associated with it. Electron 54 is located within K shell 56.

Primary x-ray or gamma ray photon 40 impacting atom 48 has a given energy. If that energy is greater than the binding energy level of K shell 56, the energy of x-ray photon 40 is absorbed by atom 48, and one of the electrons in K shell 56 (i.e., electron 54) is ejected. With a vacancy now in K shell 56 left by electron 54, atom 48 is energetic and unstable. To become more stable, that vacancy in K shell 56 can be—and usually is—filled by an electron located in a shell with a lower binding energy level, such as L-shell electron 58 in L shell 60. As L-shell electron 58 fills the vacancy in K shell 56, atom 48 emits a secondary x-ray photon 44. The energy levels (or corresponding wavelengths) of such secondary x-ray photons are uniquely characteristic to each taggant, allowing the presence or absence of any specific taggant to be determined.

The at least one taggant can be intrinsically or extrinsically present in the product to be detected and/or its packaging (collectively, the “target material”). When the taggant(s) is intrinsically present, it is a component (either as an element, compound, or other type of composition) in at least one portion of that target material. When the taggant(s) is extrinsically present, it can be added, incorporated, or inserted into the target material as described below.

The at least one taggant employed in the present invention can be any suitable taggant known in the art. See, for example, U.S. Patent Nos. 5,474,937, 5,760,394, and 6,025,200, the disclosures of which are incorporated herein by reference. Suitable taggants include any element or compound which is capable of being detected via XRF. The type of elements that can be used as the taggant are theoretically any of those listed in the periodic table, but the lower energy emitted by electrons in the lower atomic-number elements could be a limiting factor. Such lower energies can be re-absorbed much easier into its own material matrix or, in some cases, into the ambient atmosphere (e.g. air). Further, different isotopes of an element, as well as elements which “excite” only under certain conditions—such as specific temperature

ranges—could be employed as the taggant in the present invention. Example of taggants that could be used in the present invention include any element with an atomic number ranging from 6 to 94. Preferably, rare earth metals are used as the at least one taggant in the present invention. More preferably, gadolinium (Gd) or lanthanum (LA) is used as the at least one taggant in the present invention.

The type of taggant depends, among other things, on the target material in which it is located. The target material can interfere with the XRF detection because, as described below, backscattering and peaks emitted by the composition of the target material during XRF analysis can interfere with the taggant peaks. For example, if paper packaging contained an As taggant and trace amounts of Pb existed in the paper, the K-level electrons of As and L-level electrons of Pb could give confusing readings during XRF detection.

In one aspect of the invention, the type of taggant should be selected based on the ability of the taggant and/or the substance in which it is located (i.e., a coating) to attach or bond to the target material. In many instances, the target material will be used, handled, and/or washed extensively. If the taggant (or the substance in which is located) is removed from the target material under such conditions, tagging the target material is of little value. For example, if a film or coating (e.g., ink) containing a taggant is applied to a target material (e.g., paper), the taggant and coating should be selected so that they will not be removed by the conditions to which the target material is periodically subjected (e.g., extensive contact with hands). Preferably, the coating and/or the taggant is selected in this aspect of the invention so that it chemically attaches or bonds to the target material, like paint attaches and bonds with a wall.

In another aspect of the invention, the type of taggant can be selected based on the ability of the taggant and/or the substance in which it is located (i.e., a coating) to be removed from the target material. In many instances, the purpose for which the target material is tagged will be temporary. After this purpose is completed, the taggant is no longer needed and can optionally be removed. For example, if an identifying film or coating containing a taggant is applied to a target material, once

the target material has been identified, the identifying film of coating may no longer be needed and can be removed by suitable means. Preferably, the coating and/or the taggant is selected in this aspect of the invention so that it is removable by mechanical or chemical means.

5 The amount and concentration of the taggant in the target material can also vary depending on the number of elements used and energy needed. The amount of taggant employed in the present invention is determined by the minimum amount needed for XRF detection. Additional amounts of taggant can be used as described below. The concentration of the taggant is at least about 1 part per million (ppm), and
10 can range from about 1-100 ppm. Larger taggant amounts can be used, but for economic reasons, a small amount is sufficient. Even lower taggant concentrations can be used (i.e., less than 1 ppm) as improved XRF devices and techniques become available.

 The form of the taggant in the target material can also vary. The form can be
15 any compound (i.e., salt) or molecule—either small or large—containing the element that is added by itself or with other components. Indeed, the taggant can be combined with various components and/or additives to make a mixture and/or solution. These other components or additives can be selected for various purposes, e.g., to modify the XRF properties, to modify the ability to be inserted into an article/product, to stabilize
20 the mixture or solution, or other purpose known in the chemical arts.

 In one aspect of the invention, the at least one taggant is a combination or plurality of taggants. A plurality of taggants could include more than one taggant of the same type, e.g., the same element or compound. A combination of taggants could also be more than one type of taggant, e.g., a different element or compound in
25 different media. For example, a taggant dispersed in ink which has been placed on paper which also contains the same or different taggant. The plurality of taggants could also include a combination of at least one intrinsic and at least one extrinsic taggant.

 The at least one taggant incorporated in the target material can provide a
30 distinctive code. Such a code could be based on the number and types of taggants

present or absent, an abundance ratio (i.e., concentrations) of the same or different taggants, the location of the taggants within the material (i.e., a barcode made of a series of taggants with a space, where the space could be part of the code), the presence of multiple types or forms of a single taggant, or a combination thereof.

5 As one example of such a code, the present invention can include a system in which the concentration of one taggant in a targeted material is controlled to provide a distinctive code. For example, for tagging ten commercially prepared batches of carpeting, the taggant yttrium oxide can be used. Ten unique codes could then be created for these ten batches by preparing samples of the target material containing
10 various concentrations (i.e., 10 ppm, 20 ppm, ... 100 ppm) of that taggant.

 The number of unique codes available with the use of just a single taggant depends on the precision with which that concentration can be controlled and measured in the sample. For example, if techniques allow concentrations in about 10 ppm increments, 10 unique codes (i.e., 10 ppm, 20 ppm, ... 100 ppm) can readily be
15 constructed from a single taggant for that concentration range. Additional codes could be created for larger concentration ranges, e.g., 100 codes of a concentration ranging from 10 ppm to 1000 ppm in 10 ppm increments. With the advent of superior concentration and detection techniques (e.g, for smaller increments), more codes may be constructed.

20 Further, the number of unique codes can be increased by adding additional types and concentrations of the same or different taggants. A significant increase in the number of possible codes can be achieved by using more than one taggant in creating the code. For example, the code can be expanded by adding another taggant with its own specific concentrations. The number of codes can be further expanded
25 by adding a third taggant with its own specific concentrations. Additional taggants could be used to provide even more codes. This coding system depends on the concentration increments of each of the taggants.

 The number of codes available in the coding system could also be increased by varying the location of the taggant(s) within the material to be detected. For example,
30 the detected material could be divided into any number of portions (i.e., quadrants)

with certain taggants (or codes) being placed in certain of those portions, and optionally not in others, to signify additional information during the XRF analysis.

When taggants include elements or compounds that may be found in the target material or in the environment to which the target material may be exposed, taggant contamination may occur and possibly render the taggant code difficult to read. For example, if the taggant comprising yttrium oxide is located in carpet as the targeted material, it is possible that additional amounts of the taggant(s) could be present in the targeted material as a result of environmental contamination, an internal chemical reaction, or other contamination. If this contamination occurs, there will be a change in the concentration of that taggant in the target material. Subsequent measurement of this taggant could yield a value corresponding to an incorrect code.

In such an instance, it is difficult to determine what amount of the taggant present in the targeted material is "contamination" as opposed to taggant present before contamination. This problem can be solved in target materials for which contamination might be suspected by using a backup (i.e., duplicate or otherwise) or secondary system, such as a backup or secondary taggant(s), backup or secondary code, or backup or secondary location. See, for example, the description in U.S. Patent No. 5,760,394, the disclosure of which is incorporated herein by reference. If desired, more than one such backup or secondary system can be used. The backup or secondary system can also be used for other purposes, e.g., to verify the original coding system.

Any suitable target material can be employed in the present invention. Suitable target materials include those which intrinsically contain the desired taggant(s) or in which the desired taggant(s) can be incorporated. Because XRF detection measures changes in the inner shell(s) of the taggant, it will not be significantly modified by chemical reactions which normally occur in the outer shells. Thus, it possible to tag chemicals and have the taggant code be carried in any product manufactured with those chemicals. Target materials should be comprised of a material in which XRF detection is easy, e.g., little chance of background

contamination, taggant deterioration, taggant destruction, contamination, or other deteriorating condition.

Example of suitable target materials include: paper products like documents, currency, or tickets; solid products like jewelry, carpets, packaging (films, labels, and adhesives), metals, rubbers (tires), woods, or plastics (credit cards); liquid products like lubricating fluids, resins, sprays, paints, oils, inks; hazardous wastes; drugs or pharmaceuticals; gaseous products; or combinations or hybrids of these materials. Additionally, suitable target materials—such as paper documents, drugs, or counterfeit manufactured items—include those that will be subsequently changed. For example, a target material that is suspected might be destroyed could be tagged with elements known to be present in the residue from the destruction. Since the taggant is not usually changed by the chemical process in destruction, a connection between the target material and its residue could be established after destruction. Preferably, the target material of the present invention is carpeting and carpet products.

The target materials containing the at least one taggant can be used for a wide number of applications. For example, tagging paints would allow any article coated with that paint to be identified. In another example, tagging paper and ink used in the paper (or applied to the paper) can be used to establish the authenticity of documents and currency. In yet another example, many manufactured items prone to counterfeiting or theft could benefit from tagging. Tagged threads in clothing could be used to encode information about the date, time, and place of manufacture. Tagging the bulk materials used in the manufacture of such items as compact disks, computer disks, video tapes, audio tapes, electronic circuits, and other items would be useful in tracing and prosecuting theft and counterfeiting cases involving these items. Tagging the packaging placed on products would allow quick and easy tracking of the packaged products.

In the present invention, the at least one taggant can be incorporated into the target material in any suitable form. Suitable forms include those which place that taggant in the target material with little to no damage (either chemical or physical) to

the target material. See, for example, the description in U.S. Patent Nos. 5,208,630, 5,760,394, and 6,030,657, the disclosures of which are incorporated herein by reference. Other suitable forms include using materials containing the taggant such as particulates like microparticles; solvents; coatings and films; adhesives; sprays; or a hybrid or combination of these methods. In any of these forms, the at least one taggant can be incorporated by itself or with another agent.

The at least one taggant can be incorporated in the target material using any suitable technique. Many existing tagging techniques involve the use of microparticles containing the elements, or compounds or compositions of the elements, comprising the at least one taggant. Additionally, particles can be manufactured wherein smaller particles, or compounds or compositions of the elements, containing the taggant. Such particles could be made of: magnetic or fluorescent materials to facilitate collection; refractory materials to enhance particle survival in an explosion; or chemically inert materials to enhance particle survival in a chemical reaction. Indeed, such particles could be made of non-durable, soluble, or reactive materials to enhance taggant dispersal in a fluid, aerosol, or powder system.

When the target material is a liquid article like paints, inks, or adhesives, or has a liquid component, the at least one taggant can be incorporated as an element or compound in solution with the liquid. Thus, the at least one taggant can be incorporated in elemental or compound form either in solution or suspension in the target material. The at least one taggant could also be dissolved or suspended in a solvent used in making the target material so that when that solvent evaporates, the residue left behind would contain the at least one taggant.

The taggant can be inserted into the target material of an article either during or after the article (or a part thereof) has been manufactured. The taggant can be manufactured as a component of the article or as part of a component of the article. During manufacture, the at least one taggant can also be incorporated into another material which comprises part of the article. Indeed, the at least one taggant could also be an element or compound of the article itself. The taggant can be incorporated into any location (including surfaces) of the article. Two (and three) dimensional

shapes and patterns of the at least one taggant can be constructed using any desired combination of types and numbers of taggants.

The at least one taggant could also be incorporated after manufacture of the target material of the article. The taggant can be implanted into the article or deposited as a coating or film on the article. Additionally, the at least one taggant could be incorporated into the already formed article as a dopant.

As a coating or film, the at least one taggant could be physically or chemically deposited by itself. The at least one taggant could also be incorporated as one ingredient (or contaminant) of another material (such as a mixture or solution) which forms a coating or film. In this aspect of the invention, the at least one taggant can be incorporated as an element or compound in solution (or suspension) with a liquid which is applied, such as by spraying, to the article. For example, the at least one taggant could be dissolved or suspended in a solvent so that when that solvent evaporates after being applied to the article, the residue left behind would contain the at least one taggant.

As apparent from the description above, the present invention has the ability to easily tag small batches of target materials with a code unique to that batch. This can be done manually or in an automated system where each batch (or select batches) of the target material receives a different code. For example, 1000 (or 100) compact discs could be manufacture and each could be tagged with a code of a number from 1 to 1000-(or 1 to 100). Economic and processing considerations, however, might limit the minimum size of each batch and the number of batches which could be tagged.

As described above, any product or article as the target material can have at least one extrinsic or intrinsic taggant located therein. For example, the target material of the present invention could be packaging and packaging products in one aspect of the invention. Examples of packaging and packaging products in which the at least one taggant could be intrinsically or extrinsically present include adhesives, boxes, labels, and wrapping, made of shrink-wrap materials, plastic materials, cardboards, laminates, papers, and the like.

In one aspect of the invention, the at least one taggant can be extrinsically or intrinsically present in any or all materials used for packaging. Examples of such packaging materials include boxes, wrapping, covers, films, coatings, and the like, as well as supplementary materials (since they supplement the packaging) such as tapes, adhesives, labels, inks, and the like.

The at least one taggant could be incorporated into packaging materials with each batch of material, if desired, having its own code. As one example, the paper label, adhesive, and/or cardboard box could have the at least one taggant incorporated therein. The taggant could be incorporated into the cardboard, paper, and/or adhesive material by injecting a solid (i.e., microparticle) or liquid (e.g., solvent) containing the at least one taggant into a component of the packaging material, e.g., the bulk material used in manufacturing the packaging. When the respective bulk material is used to make the cardboard, label, or adhesive (glue), the resulting packaging material(s) will contain the at least one taggant. Assuming six taggants will be used (two for the cardboard, two for the paper label, and two for the glue) a number of automated reservoirs having varying concentrations of the two taggants could be included in the assembly line process for each bulk material. Each reservoir would contain the distinctive mix of taggant concentrations, e.g., 5/5, 5/10, 5/15,...10/5, 10/10, 10/15, ... 95/85, 95/90, 95/95. As the sample of the respective bulk material passes through the assembly line, it would receive the taggants from the desired reservoir. Thus, packaging materials manufactured from its respective bulk material would receive a unique combination of taggants for its code.

After the at least one taggant is extrinsically or intrinsically present in the target material(s), the taggant(s) is detected to identify or verify the target material using XRF analysis as illustrated in Figure 1. Primary x-rays are used to excite a sample of the target material, and the secondary x-rays that are emitted by the sample are detected and analyzed.

As shown in Figure 3, the x-rays which are detected have various energies, e.g., there is a broad band of scattered x-rays with energies less than and greater than those of the exciting atom. Figure 3 illustrates this spectrum for paper as the target

material. Within this broad band, there are peaks due to the excitation of the taggant(s) in the sample. The ratio of the intensity of the radiation in any peak to the intensity of the background at the same energy (known as the peak-to-background ratio) is a measure of the concentration of the element which has characteristic X-rays at the energy of that peak, e.g., the taggant.

In one aspect of the detection method of the present invention, at least one target material believing to contain known concentrations of the taggant(s) of interest is selected. The XRF analysis is performed on that target material (or a sample thereof) using a detection device or apparatus containing an x-ray radiation source ("source"), x-ray radiation detector ("detector"), support means, analyzer means, and calibration means.

One aspect of the detection device of the present invention is illustrated in Figure 4a. In this Figure, the detection apparatus 25 has an ordinary x-ray fluorescence spectrometer capable of detecting elements present in a coating, package or material. X-rays 29 from a source (e.g., either x-ray tube or radioactive isotope) 20 impinge on a sample 11 which absorbs the radiation and emits x-rays 31 to an x-ray detector 21 and analyzer 23 capable of energy or wavelength discrimination. This is accomplished by using a commercially available x-ray spectrometer such as an Edax DX-95 or a MAP-4 portable analyzer, commercially available from Edax Inc., Mahwah, New Jersey. Part of analyzer 23 includes a computerized system 27.

Another aspect of the detection apparatus of the present invention is illustrated in Figure 4b. In this Figure, the detection apparatus 25 has an instrument housing 15 which contains the various components. Gamma rays or x-rays 30 from a source (e.g., either x-ray tube or radioactive isotope) 20 are optionally focused by aperture 10 to impinge on a sample 11. Sample 11 contains the at least one taggant which absorbs the radiation and emits x-rays 31 to an x-ray detector 21. Optionally, analyzing means can be incorporated within housing 15.

The present invention, however, is not limited to the detection apparatus depicted in Figures 4a and 4b. Any suitable source, or plurality of sources, known in the art can be used as the source in the detection device of the present. See, for

example, U.S. Patent Nos. 4,862,143, 4,045,676, and 6,005,915, the disclosures of which are incorporated herein by reference. During the XRF detection process, the source bombards the taggant with a high energy beam. The beam may be an electron beam or electromagnetic radiation such as X-rays or gamma rays. The source, therefore, may be any material which emits such high energy beams. Typically, these have been x-ray emitting devices such as x-ray tubes or radioactive sources.

To target, the beam can be focused and directed properly by any suitable means such as an orifice or an aperture. The configuration (size, length, diameter...) of the beam should be controlled, as known in the art, to obtain the desired XRF detection. The power (or energy level) of the source should also be controlled, as known in the art, to obtain the desired XRF detection.

The source(s) can be shielded and emit radiation in a space limited by the shape of the shield. Thus, the presence, configuration, and the material used for shielding the source should be controlled for consistent XRF detection. Any suitable material and configuration for that shield known in the art can be employed in the present invention. Preferably, any high-density materials used as the material for the shield, e.g, tungsten or brass.

Any suitable detector, or plurality of detectors, known in the art can be used as the detector in the detection device of the present invention. See, for example, U.S. Patent Nos. 4,862,143, 4,045,676, and 6,005,915, the disclosures of which are incorporated herein by reference. Any type of material capable of detecting the photons omitted by the taggant may be used. Silicon and CZT (cadmium-zinc-telluride) detectors have been conventionally used, but others such as proportional counters, germanium detectors, or mercuric iodide crystals can be used.

Several aspects of the detector should be controlled to obtain the desired XRF detection. First, the geometry between the detector and the target material should be controlled. The XRF detection also depend on the presence, configuration, and material—such as tungsten and beryllium—used as a window to allow x-rays photons to strike the detector. The age of the detector, voltage, humidity, variations in

exposure, and temperature can also impact the XRF detection and, therefore, these conditions should be controlled.

The analyzer means sorts the radiation detected by the detector into one or more energy bands and measures its intensity. Thus, any analyzer means performing this function could be used in the present invention. The analyzer means can be a multi-channel analyzer for measurements of the detected radiation in the characteristic band and any other bands necessary to compute the value of the characteristic radiation as distinct from the scattered or background radiation. See, for example, U.S. Patent Nos. 4,862,143, 4,045,676, and 6,005,915, the disclosures of which are incorporated herein by reference.

The XRF also depends on the resolution of the x-rays. Background and other noise must be filtered from the x-rays for proper measurement, e.g., the signals must be separated into the proper number of channels and excess noise removed. The resolution can be improved by cooling the detector using a thermoelectric cooler—such as nitrogen or a peltier cooler—and/or by filtering. Another way to improve this resolution is to use pre-amplifiers.

The support means supports the source and detector in predetermined positions relatively to a sample of the target material to be irradiated. Thus, any support means performing this function could be used in the present invention. In one example, the support means comprises two housings, where the source and detector are mounted in a first housing which is connected by a flexible cable to a second housing in which the analyzer means is positioned as illustrated in Figure 4a. If desired, the first housing may then be adapted to be hand-held. In another example, the source and detector as well as the other components of the detection device are mounted in a single housing as illustrated in Figure 4b.

The calibration means are used to calibrate the detection apparatus, thus insuring accuracy of the XRF analysis. In this calibration, the various parameters which could be modified and effect the measurement are isolated and calibrated. For example, the geometrical conditions or arrangements can be isolated and calibrated. In another example, the material matrix are isolated and calibrated. Preferably,

internal (*in situ*) calibration during detection is employed as the calibration means in the present invention. Components, such as tungsten shielding, are already present to internally calibrate during the XRF analysis. Other methods, such as fluorescence peak or Compton backscattering, could be used for internal calibration in the present invention.

Analyzer means, which includes a computerized system 27, is coupled to, receives, and processes the output signals produced by detector 21. The energy range of interest, which includes the energy levels of the secondary x-ray photons 44 emitted by the taggant(s), is divided into several energy subranges. Computerized system 27 maintains counts of the number of X-ray photons detected within each subrange using specific software programs, such as those to analyze the detection and x-ray interaction and to analyze backscatter data. After the desired exposure time, computerized system 27 with display menus stops receiving and processing output signals and produces a graph of the counts associated with each subrange.

Figure 5 is a representative graph of the counts associated with each subrange. This graph is essentially a histogram representing the frequency distribution of the energy levels E1, E2, and E3 of the detected x-ray photons. Peaks in the frequency distribution (i.e., relatively high numbers of counts) occur at energy levels of scattered primary x-ray photons as well as the secondary x-ray photons from the taggant(s). A primary x-ray photon incident upon a target material may be absorbed or scattered. The desired secondary x-ray photons are emitted only when the primary x-ray photons are absorbed. The scattered primary x-ray photons which reach the detector of the system create an unwanted background intensity level. Accordingly, the sensitivity of XRF analysis is dependent on the background intensity level, and the sensitivity of XRF detection may be improved by reducing the amount of scattered primary x-ray photons reaching the detector. The peak occurring at energy levels of scattered primary x-ray photons is basically ignored, while the other peaks—those occurring at E1, E2, and E3—are used to identify the at least one taggant present in the target material.

Besides the parameters described above, at least two other parameters must be controlled during the process of XRF detection. First, the media (such as air) through which the gamma rays (and x-rays) must travel also impacts the XRF. Therefore, the different types of media must be considered when performing the XRF analysis. Second, the methods used to interpret and analyze the x-rays depend, in large part, on the algorithms and software used. Thus, methods must be adopted to employ software and algorithms that will consistently perform the XRF detection.

These two parameters, plus those described above, must be carefully accounted for and controlled to obtain accurate measurements. In one aspect of the intention, these parameters could be varied and controlled to another provide a distinct code. For example, using a specific source and a specific detector with a specific measuring geometry and a specific algorithm could provide one distinct code. Changing the source, detector, geometry, or algorithm could provide a whole new set of distinct codes.

Figure 6 illustrates a preferred apparatus and detection method according to the present invention. In this Figure, detection apparatus 25 is capable of detecting at least one taggant present in packaging supplementary material, such as label 4 for a VCR tape 2. Detection apparatus 25 is a portable device which can be small enough to be hand-held. Detection apparatus 25 contains all the components discussed above (i.e., source, detector, analyzer means, and calibration means) in a single housing, thus allowing the portability and smaller size.

In Figure 6, VCR tape 2 had a tagged label 4 placed thereon using an adhesive (not shown). The VCR tape is enclosed in cover 8, along with paper brochures as advertising. The cover 8 is, in turn, covered with shrink wrap tape 10 as well as cardboard box 12. Detection apparatus 25 is able to detect the presence of the taggant(s) in label 4 even though the label is not in "line-of-sight" with the apparatus. Although not depicted in the aspect of the present invention shown in Figure 6, box 12, wrap 10, cover 8, and tape 2 could also have at least one taggant incorporated therein.

The present invention is not limited to any specific XRF analysis. Any type of XRF, such as total reflection x-ray fluorescence (TXRF), can be employed in the present invention.

5 In one aspect of the invention, the apparatus and method used identify an article once it has been tagged. The ability to invisibly tag an article and read the tag, especially through a non line-of-sight method, would provide an invaluable asset in any industry which authenticates, verifies, tracks, labels, or distributes goods of any kind. Indeed, having an invisible taggant(s) could further prevent copying and counterfeiting of goods. In another aspect of the invention, the apparatus and method
10 of the present invention could be used for these same purposes, but for those products which have the desired taggant already located therein. Thus, the present inventions could analyze liquid flows for contaminant particles or pinpoint via 3-D analysis the exact location of a contaminant(s) in an article.

The following non-limiting examples illustrate the present invention.

Example 1

15 A blank VCR tape with a plastic cover was purchased and the cover removed. A self-adhesive label was prepared for the tape. A taggant solution was then prepared by mixing 5 milliliters of adhesive solution with 0.352 grams of LaO_2 until a
20 homogenous mixture was obtained. The concentration of the taggant in the taggant solution was 5 wt%.

The taggant solution was then coated on the back of the label by hand and the label was then affixed to the VCR tape, and the plastic cover was then placed back on the tape. The cover was then shrink-wrapped with plastic tape and then placed inside
25 a cardboard box.

Example 2

The tagged adhesive on the label for the VCR from Example 1 was analyzed for the presence of the taggant. A portable, hand-held detection apparatus similar to

that illustrated in Figure 6 was used to detect the presence of the taggant using XRF analysis.

5 The detection apparatus contained several components. A trigger actuated tungsten shutter block containing an americium 241 gamma ray point source and a silicon pin x-ray detector were located within the front of the instrument. Circuit boards, necessary for acquiring and processing the data from the detector were located within the rest of the housing. The instrument had a red and a green light to indicate whether the carpet was tagged or not and a read out to inform the user that the carpet was tagged or not. A keypad on the top of the instrument allowed the user to turn the
10 electronics of the instrument on and off, while a key operated lock on the side of the instrument kept the user from inadvertently opening the shutter block, exposing the radioactive source.

This detection apparatus was used for an XRF analysis on the tagged sample. The result of the XRF analysis is reported in Figure 7. The peaks indicating the
15 presence of the LaO_2 taggant in Figure 7 are labeled.

Having described the preferred aspects of the present invention, it is understood that the invention defined by the appended claims is not to be limited by particular details set forth in the above description, as many apparent variations thereof are possible without departing from the spirit or scope thereof.

CLAIMSI claim:

1. A method for detecting at least one taggant in the packaging material
5 for an article, comprising:

providing the at least one taggant in at least a portion of the packaging
material;

causing the at least one taggant to radiate at least one x-ray; and
analyzing whether the at least one x-ray has a specific energy.

2. The method of claim 1, wherein the packaging material is at least one
10 label.

3. A method of analyzing the packaging material for an article,
comprising

providing at least a portion of a packaging material on or over a portion of an
15 article;

irradiating the packaging material portion with an energy beam; and
analyzing whether the packaging material portion irradiates at least one x-ray
with a specific energy.

4. The method of claim 3, wherein the packaging material is at least one
20 label.

5. A method for packaging an article, comprising:
providing a portion of an article; and
providing at least a portion of a packaging material on or over a portion of the
article, the packaging material portion comprising at least one taggant which radiates
25 at least one x-ray when an energy beam is impinged thereon.

6. The method of claim 5, wherein the packaging material is at least one
label.

7. Packaging material for an article, the packaging material comprising at
least one taggant which radiates at least one x-ray when an energy beam is impinged
30 thereon.

8. The packaging material of claim 7, wherein the packaging material is at least one label.

9. A method for manufacturing a packaging material containing at least one taggant, comprising:

5 providing a component of the packaging material;

adding at least one taggant to the component, the at least one taggant radiating at least one x-ray when an energy beam is impinged thereon; and

combining the tagged component with other components of the packaging material.

10 10. A method for manufacturing a packaging material containing at least one taggant, comprising:

providing at least a portion of a packaging material; and

adding at least one taggant to the packaging material portion, wherein the at least one taggant radiates at least one x-ray when an energy beam is impinged thereon.

15 11. A method of manufacturing a packaged article containing at least one taggant, comprising:

providing a portion of an article; and

providing a portion of a packaging material on or over a portion of the article, the packaging material comprising at least one taggant which radiates at least one x-ray when an energy beam is impinged thereon.

20

12. The method of claim 11, wherein the packaging material is at least one label.

13. A packaged article containing at least one taggant made by the method comprising:

25

providing a portion of an article; and

providing a portion of a packaging material on or over a portion of the article, the packaging material comprising at least one taggant which radiates at least one x-ray when an energy beam is impinged thereon.

14. The packaged article of claim 13, wherein the packaging material is at least one label.

15. An article comprising a packaging material containing at least one taggant which radiates at least one x-ray when an energy beam is impinged thereon.

16. The article of claim 15, wherein the packaging material is at least one label.

17. A method of tagging an article with at least one taggant comprising:
providing a portion of an article; and
providing a portion of a packaging material on or over a portion of the article, the packaging material comprising at least one taggant which radiates at least one x-ray when an energy beam is impinged thereon.

18. The method of claim 17, wherein the packaging material is at least one label.

19. A packaging material containing at least one taggant made by the method comprising:

providing a component of the packaging material;
adding at least one taggant to the component, the at least one taggant radiating at least one x-ray when an energy beam is impinged thereon; and
combining the tagged component with other components of the packaging material.

20. A packaging material containing at least one taggant made by the method comprising:

providing at least a portion of a packaging material; and

adding the at least one taggant to the packaging material portion, wherein the at least one taggant radiates at least one x-ray when an energy beam is impinged thereon.

1/7




FIG. 1




FIG. 2b




FIG. 2a

2/7




FIG. 3





FIG. 4a

25
↓



4/7

FIG. 4b




FIG. 5




FIG. 6




FIG. 7

INTERNATIONAL SEARCH REPORT

International application No.

PCT/US00/27492

A. CLASSIFICATION OF SUBJECT MATTER

IPC(7) : G01N 23/223

US CL : 378/44, 45

According to International Patent Classification (IPC) or to both national classification and IPC

B. FIELDS SEARCHED

Minimum documentation searched (classification system followed by classification symbols)

U.S. : 378/44, 45, 48, 49, 50

Documentation searched other than minimum documentation to the extent that such documents are included in the fields searched
NONE

Electronic data base consulted during the international search (name of data base and, where practicable, search terms used)
NONE

C. DOCUMENTS CONSIDERED TO BE RELEVANT

Category *	Citation of document, with indication, where appropriate, of the relevant passages	Relevant to claim No.
Y	US 4,485,308 A (RABATIN) 27 November 1984 (27.11.1984), column 3, lines 23-53.	1-20
Y	US 4,136,778 A (WORTMAN et al.) 30 JAN. 1979 (30.01.1979) column 4, lines 10-30.	1-20
A	US 4,445,225 A (WHITE) 24 April 1984 (24.04.1984) entire document.	1-20

☐ Further documents are listed in the continuation of Box C.

☐ See patent family annex.

* Special categories of cited documents:

- "A" document defining the general state of the art which is not considered to be of particular relevance
- "E" earlier application or patent published on or after the international filing date
- "L" document which may throw doubts on priority claim(s) or which is cited to establish the publication date of another citation or other special reason (as specified)
- "O" document referring to an oral disclosure, use, exhibition or other means
- "P" document published prior to the international filing date but later than the priority date claimed

- "T" later document published after the international filing date or priority date and not in conflict with the application but cited to understand the principle or theory underlying the invention
- "X" document of particular relevance; the claimed invention cannot be considered novel or cannot be considered to involve an inventive step when the document is taken alone
- "Y" document of particular relevance; the claimed invention cannot be considered to involve an inventive step when the document is combined with one or more other such documents, such combination being obvious to a person skilled in the art
- "&" document member of the same patent family

Date of the actual completion of the international search

24 January 2001 (24.01.2001)

Date of mailing of the international search report

09 FEB 2001

Name and mailing address of the ISA/US

Commissioner of Patents and Trademarks
Box PCT
Washington, D.C. 20231

Facsimile No. (703) 305-3230

Authorized officer

David P. Porta

Telephone No. (703) 308-0956

Shawn J. Hoppe

**This Page is Inserted by IFW Indexing and Scanning
Operations and is not part of the Official Record**

BEST AVAILABLE IMAGES

Defective images within this document are accurate representations of the original documents submitted by the applicant.

Defects in the images include but are not limited to the items checked:

☐ BLACK BORDERS

☒ IMAGE CUT OFF AT TOP, BOTTOM OR SIDES

☐ FADED TEXT OR DRAWING

☐ BLURRED OR ILLEGIBLE TEXT OR DRAWING

☐ SKEWED/SLANTED IMAGES

☐ COLOR OR BLACK AND WHITE PHOTOGRAPHS

☐ GRAY SCALE DOCUMENTS

☐ LINES OR MARKS ON ORIGINAL DOCUMENT

☒ REFERENCE(S) OR EXHIBIT(S) SUBMITTED ARE POOR QUALITY

☐ OTHER: _____

IMAGES ARE BEST AVAILABLE COPY.

As rescanning these documents will not correct the image problems checked, please do not report these problems to the IFW Image Problem Mailbox.